

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: K & N Petroleum, Inc.

Address: 1105 Walnut, Great Bend, KS 67530

Phone: (620) 793-6005 Operator License #: 3208

Type of Well: Oil Well Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: February 21, 2007 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 009-04491-00-00

Lease Name: Friedley/Rick

Well Number: #2

Spot Location (QQQQ): E2 - NW - NE -
4820 Feet from North / South Section Line
1650 Feet from East / West Section Line

Sec. 12 Twp. 19s S. R. 11 East West

County: Barton

Date Well Completed: 07/01/1959

Plugging Commenced: 02/22/07

Plugging Completed: 02/23/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	N/A	8-5/8"	N/A	170' per 0' cap 2/3 per KCC 3/5/07
	Production	0'	3334'	5-1/2"	3334'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran in tubing to 2000'. Put in stripper rubber. Shut down for the night. Dug head out on surface pipe - it was full of cement. Pumped 100 sacks 60/40 poz mix, 10% gel cement with 300 lbs. hulls. Pulled to 1300'. Pumped 100 sacks 60/40 poz mix, 10% gel cement with 200 lbs. hulls. Circulated cement. Pulled out tubing. Squeezed well with 400 lbs. pressure. Shut in with 200 lbs. Pumped a total of 265 sacks 60/40 poz mix, 10% gel cement and 500 lbs. hulls. Rigged down and moved off.


Name of Plugging Contractor: D.S. & W. Well Servicing, Inc. License #: 6901

Address: P.O. Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: K & N Petroleum, Inc.

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]

(Address) 1105 Walnut, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 27th day of February, 20 07

[Signature] My Commission Expires: 4/13/2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 01 2007
CONSERVATION DIVISION
WICHITA, KS