

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Timberline Oil & Gas Corporation
Address: 4000 Penrose Place Rapid City, S.D. 57702
Phone: (605) 341-3400 Operator License #: 9232
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Steve Pfiefer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-151-10657-00-00
Lease Name: Binger *KCC PKF PR1 CP-2/3 3-6-07*
Well Number: 3
Spot Location (OQQQ): _____ NE _____ NW
4620 Feet from _____ North / South Section Line
3300 Feet from East / _____ West Section Line
Sec. 31 Twp. 26 S. R. 12 _____ East West
County: Pratt
Date Well Completed: _____
Plugging Commenced: 2-1-07
Plugging Completed: 2-8-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	621'	None
				7"	4297'	1810'


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.
Plugged off bottom with sand to 3070' and 7 sxs. cement. Cut casing loose @1810', pulled up to 650', pumped 15 sxs. gel & 50 sxs. cement, pulled up to 300', pumped 50 sxs. cement, pulled up to 300', pumped 50 sxs. cement, pulled up to 40' & circulated 40 sxs. to surface.
Plugging Complete. 60/40 pos, 6% gel.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Timberline Oil & Gas Corporation
State of Kansas County: Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above described well being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 2nd. day of March, 20 07
Irene Herzberg My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 05 2007

KCC WICHITA

PKF