

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Novy Oil & Gas, Inc.
Address: 125 N. Market, Suite 1230, Wichita, KS 67202
Phone: (316) 265-4651 Operator License #: 31714
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: January 12, 2007 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: _____ Bottom: 3295' T.D. 3298'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-21831-00-00
Lease Name: Isen
Well Number: #1 **KCC**
Spot Location (QQQQ): SW - SW - SW - P1C7 **3-7-07**
330 Feet from ☐ North / ☒ South Section Line **P1C1**
330 Feet from ☒ East / ☐ West Section Line **CP2/3**
Sec. 25 Twp. 19S S. R. 11 ☐ East ☒ West
County: Barton
Date Well Completed: 01/08/80
Plugging Commenced: 02/08/07
Plugging Completed: 02/09/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	surface	0'	<u>175' 212</u>	8-5/8"	175'	0
	production	0'	<u>3209'</u>	4-1/2"	3209'	1400'
			<u>3295'</u>			

Per CP2/3 P1C7 3/7/07

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Ran in 2-7/8" mill on bottom & 34 jts. to 1037'. Shut down and tore down off well. Have safety meeting. Come back and rigged up. Waited on Allied Cement. Spot 125 sacks cement with 300# hulls at 1037'. Pull up to 550', spot 25 sacks cement with 100# hulls. Pull up to 250', spot 40 sacks cement with 100# hulls. Pull up to 30' and circulate 60 sacks cement to surface, pulling out rest of tubing and hole standing full. R.D.M.O.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc. License #: 6901
Address: P.O. Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: Novy Oil & Gas, Inc.
State of Kansas County, Sedgwick, ss.

Michael E. Novy, Vice President, Novy Oil & Gas, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Michael E. Novy
(Address) 125 N. Market, Suite 1230, Wichita, KS 67202

RECEIVED
MAR 06 2007

KCC WICHITA

SUBSCRIBED and SWORN to before me this 2nd day of March, 20 07
Connie L. Crook My Commission Expires: 12-12-2008
Notary Public