

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-10218-00-00  
Spot: SWSW Sec/Twnshp/Rge: 16-30S-34W  
660 feet from S Section Line, 660 feet from W Section Line  
Lease Name: STEVENS J C Well #: 3  
County: HASKELL Total Vertical Depth: 5800 feet

Operator License No.: 4549  
Op Name: ANADARKO PETROLEUM CORPORATI  
Address: 1201 LAKE ROBBINS DRIVE  
THE WOODLANDS, TX 77380

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	13.38	568		
PROD	5.5	5460	2294	WITH 500 SX CMT
SURF	8.625	1775		WITH 600 SX CMT

\$ 188.50

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/09/2007 10:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. DISPLACE WITH MUD. PRESSURE TO 500#. PLUG AT 1800' WITH 50 SX CMT. PLUG AT 630' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT. CHECK 8 5/8" X 13 3/8" ANNULUS.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/15/2007 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 300# HULLS & 25 SX CMT ON BOTTOM. 1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5367	5381		

**INVOICED**  
DATE 3-5-07  
INV. NO. 2007061423

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed

Jim Holland PART III  
(TECHNICIAN)

RECEIVED  
FEB 28 2007  
KCC WICHITA

Form CP-2/3

*[Handwritten signature]*