

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01725-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 19-9S-20W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: BALTHAZOR Well #: 2  
County: ROOKS Total Vertical Depth: 3800 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: P.O. BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3794	0	w/150 sxs cmt
SURF	8.625	187	0	w/200 sxs cmt

\$ 123.50

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/26/2007 10:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: CURT GABEL Company: BEREN COPORATION Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 800# hulls.  
Squeeze jobs: 1911'-1971' w/125 sxs; 2536'-2561' w/75 sxs.  
New casing leaks: 1372'-1388'; 1932'-1936'; 2517'-2546'; 2754'-2783'.  
AD-1 packer at 3781' - left in the hole.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/26/2007 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3750' - pumped 50 sxs 60/40 pozmix - 10% gel with 100# hulls.  
Pulled tubing to 3100' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 1800' - pumped 150 sxs cement with 300# hulls.  
Pulled tubing to 900' - pumped 72 sxs cement with 100# hulls - cement circulated.  
PTOH. Topped off with 10 sxs cement.  
Hooked up to backside - instant 300#.

Perfs:

Top	Bot	Thru	Comments
3794	3800	OH	
3557	3603		Arbuckle

**INVOICED**  
DATE 3-5-07  
INV. NO. 2007061433

Remarks: ALLIED CEMENTING COMPANY-TICKET #33204.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

FEB 26 2007

RECEIVED Form CP-2/3  
KANSAS CORPORATION COMMISSION  
MAR 01 2007  
CONSERVATION DIVISION  
WICHITA, KS

AMERADA PETROLEUM CO. #2 BALTAZOR 19-9-20W  
NW NW NE


Contr. LAURA JANE OIL COMPANY ROOKS County

E 22<sup>73</sup> Comm. Comp. 9-7-51 IP 3000 BOPD (ARB)  
DRAW DOWN

Tops		Depth	Datum
Arch	Top	1773	+500
"	Base	1211	+462
HEEB		3474	-1201
LANS		3514	-1241
ARB		3794	-1521
T.D.		3800	-1527

Casing  
5" 3795  
DST 3538-3610, 2 HRS,  
450' OIL & GAS  
CUT MUD, 20% OIL  
BHP 1250#  
ACID 1500  
SWB 119 BO/6 HRS

GRA-ROOK POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS