

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00729-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 33-10S-20W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: TRICO LKC ARBUCKLE UNIT Well #: 302
County: ROOKS Total Vertical Depth: 3733 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PARKWAY, BLDG
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3707	0	75 SX
SURF	8.625	180	0	135 SX

\$ 121.32

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2007 10:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 800# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2007 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 850' - 1600' - 2150'.
TIH with tubing to 3710' - mixed and spotted 60 sxs with 450# hulls.
Pulled up to 2790' - spotted 100 sxs with 200# hulls.
Pulled up to 1250' - circulated cement with 160 sxs cement with 150# hulls.
POOH. Topped with 20 sxs cement.
Tied onto annulus and pumped 20 sxs cement.
Max. P.S.I. 700#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3706	3733		OH
3538	3616		

INVOICED
DATE 3-5-07
INV. NO. 2007061434

Remarks: ORIGINALLY KNOWN AS VEACH #2. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

FEB 26 2007

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 01 2007
CONSERVATION DIVISION
WICHITA, KS

TRANS ERA

#2

VEACH

33-10-20W
NW NW SE

Contr. TRANS ERA

ROOKS

County

2131 RB

Comm.

Comp.

12-17-54

IP

203 BOPD

PERM PMPG

Tops	Depth	Datum
FREEB	3368	-1237
KC	3405	-1274
CONG	3653	-1522
ARB	3706	-1575
TD	3709	-1578

Casing

8" 180

5" 3706

DST 3484-93/1 HR, 30' MDY SW

BHP 550#

DST 3707-09/1 HR, 1800' FREE

OIL, BHP 995#

CO 3709: ACID 500: 5 1/2 BOPH

NAT'L: SWB 20 BOPH, NO WTR

ALLPHIN POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS