

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21136-00-00
Spot: ~~E2NWNWNE~~ ^{CePs P+95} Sec/Twnshp/Rge: 22-19S-11W
4950 feet from S Section Line, 2210 feet from E Section Line
Lease Name: HIRSCH Well #: 3
County: BARTON Total Vertical Depth: 3382 feet

Operator License No.: 5310
Op Name: FOUR-WAY OPERATING, INC.
Address: PO BOX 698
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3355	0	225 SX
SURF	10.75	209	0	150 SX

\$ 109.92

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/22/2007 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Ordered 210 sxs 60/40 pozmix - 10% gel - 350# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/22/2007 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded off bottom perms to 2810' - topped with 5 sxs cement using a dump bailer.
Cut casing at 2310' - pulled casing to 1325'.
Rigged to casing - pumped 95 sxs cement with 250# hulls mixed in.
Pulled casing to 600' - rigged to casing - pumped 40 sxs cement with 100# hulls mixed in.
Pulled casing to 150' - rigged to casing - pumped 75 sxs to circulate cement to surface.
POOH. Pulled rest of casing.
Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3355	3382		
3135	3296		
2853	2860		

INVOICED

DATE 3-5-07

INV. NO. 2007061428

RECEIVED

FEB 28 2007

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #C031653.


Plugged through: CSG

KCC WICHITA

District: 04

NO

Signed



(TECHNICIAN)

FEB 23 2007

PKT

FOUR-WAY OPERATING, INC.
 BOX 699, GREAT BEND, KS.

#3 HIPSCH

22-19-11W
 100'E. NW NW NE

CONTR. ACOTMAR-LANNITTI REG. CTY. BASTON

GEOL. _____ FIELD ANTERMAN

E. 1787 *BGM 2/4/77 CARD ISSUED 5/12/77 P. 25 BOPD + WTP
 LFB 3355-65

API 15-009-21,136-06-00

LCC	TOPS	DEPTH	DATUM
FEES		3311	-1124
BE LN		3311	-1244
LA'S		30-1	-1264
ARE		3348	-1561
TO		3355	-1576
Auth. Co.			+1238
Vote			+1213

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

10-3/4" 200/150sx, 5 1/2" 3355
 DST (1) 2257-65/30-30-30-30, 25'M, P
 757-757#, FP 71-41# 71-61#
 DST (2) 3038-80/30-30-30-30, GTS/15'
 FLO 87 MCFG, 100' GCM, SIP 647-6 #
 FP 81-102# 61-102#
 DST (3) 3088-3130/30-30-30-30, 2560'
 SOCW, SIP 1254-1254# FP 427-887#
 996-1185#
 DST (4) 3222-40/75", 40' SOCM, SIP 407-
 305# FP 51-51# 61-71#
 DST (5) 3270-3305/30-30-30-30, 30' GCM
 W/SP O, SIP 132-122# FP 30-41# 41-
 61#
 DST (6) 3310-55/30-30-30-30, 30'M W/SO
 SIP 727-602# FP 102-102# 102-102#
 (OVER)

DST (7) 3355-65/30-30-30-30, 180' OIL, 250' MCO, SIP 470-335#
 FP 71-132# 123-123#
 MIST - 20 TO, AC 500, REC LD, SWB AYC 2 BOPD + 15% W, POP