

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04491-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 12-19S-11W
4820 feet from S Section Line, 1650 feet from E Section Line
Lease Name: FRIEDLEY/RICK Well #: 2
County: BARTON Total Vertical Depth: 3356 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 513 W. 6TH ST
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3334	0	w/125 sxs cmt
SURF	8.625	170	0	w/125 sxs cmt

\$ 109.07

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2007 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: EDWARD S. NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 793-4023

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls. CIPB at 3145'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2007 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Dug out backside - removed bull plugs - backside full of cement from previous squeezes - visual check.
RIH with tubing to 2000'. Rigged to tubing - pumped 100 sxs cement with 300# hulls mixed in.
Pulled tubing to 1300'. Rigged to tubing - pumped 135 sxs cement with 200# hulls to circulate cement to surface.
Pulled tubing. Rigged to 5 1/2" casing with a swedge - pumped 30 sxs 60/40 pozmix.
Max. P.S.I. 400#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3108	3112		
3084	3088		
3072	3076		
3031	3035		

INVOICED
DATE 3-5-07
INV. NO. 2007061429

RECEIVED
FEB 28 2007
KCC WICHITA

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET C-031654.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

FEB 26 2007

[Handwritten initials]