

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-197-20100-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 29-14S-12E
4696 feet from S Section Line, 1644 feet from E Section Line
Lease Name: HARROLD Well #: 2
County: WABAUNSEE Total Vertical Depth: 3005 feet

Operator License No.: 31142
Op Name: PETROLEUM PROPERTY SERVICES, IN
Address: 125 N MARKET, STE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2997		125 SX
SURF	8.625	200		150 SX

\$ 97.66

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/08/2007 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: RONALD SCHRAEDER Company: PETROLEUM PROPERTY SERVICE Phone: (316) 265-3351

Proposed Plugging Method: SET 50' PLUG AT 3005' WITH 15 SX, 50' PLUG AT 2405' WITH 15 SX. PERFORATE AT 1345', 50' PLUG AT 1345' WITH 15 SX, PERFORATE AT 350', PUMP CEMENT DOWN THE CASING AND CIRCULATE TO SURFACE, USE 36 VIS. DRILLING MUD INBETWEEN THE PLUGS.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/08/2007 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Pumped 15 sacks of cement at 3005' and 15 sacks of cement at 2405'. Perforated the casing at 1345' and spotted 20 sacks of cement. Gel spacers were used between the plugs. Perforated the casing at 350' and circulated 30 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
2997	3005		

RECEIVED
KCC DISTRICT #3

FEB 26 2007 TCH

CHANUTE, KS

INVOICED
DATE 3-7-07
INV. NO. 2007061437

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

RECEIVED
Form CP-2/3

MAR 05 2007

KCC WICHITA

PLG