

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00943-00-00
Spot: SENESE Sec/Twnshp/Rge: 6-8S-17W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: BROWN Well #: 1
County: ROOKS Total Vertical Depth: 3364 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3353	0	w/100 sxs cmt
SURF	8.625	145	0	w/150 sxs cmt

\$109.33

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2007 2:30 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 623-0546

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 750# hulls.
Squeeze Jobs: 786' w/200 sxs; 950'-1073' w/200 sxs.
New casing leaks at 1616' and 2017'.
Unable to squeeze - decided to P/A. Emergency plug with rig over the hole.
Lockset packer at 2960' w/2 sxs sand on top of.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2007 5:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2810'. Allied pumped 100 sxs 60/40 pozmix - 10% gel with 200# hulls.
Pulled tubing to 1660'. Allied pumped 100 sxs w/300# hulls - cement circulated.
PTOH. Squeezed 5 1/2" casing with 20 sxs cement.
Max. P.S.I. 100#. S.I.P. 100#.
Hooked up to backside. Allied pumped 35 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3353	3364		OH
3228	3232		
3002	3004		

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 07 2007
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 3-8-07
INV. NO. 2007061439

Remarks: ALLIED CEMENTING COMPANY. RGN-WATER.

Plugged through: TBG

District: 04

Signed _____

Richard Williams

(TECHNICIAN)

MAR 05 2007

AKT

V. D. SIDNEY

#1 BROWN

6-8-17W
SE NE SE

Contr. _____ ROOKS _____ County

E 1898 Comm. 12-17-55 ^{Done 3-23-56} Comp. 3-23-56 IP 25 BOFD/ARB


Tops	Depth	Datum
Arh	1324	757.4
LANS	3064	-1166
ARB	3351	-1453
ID	3356	-1458

Casing

5" 3353

CO 3356: ACID 1000

LONE STAR POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS