

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23391-00-00
Spot: SWNESW Sec/Twnshp/Rge: 6-14S-14W
1575 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MAAB B Well #: 1
County: RUSSELL Total Vertical Depth: 3280 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	3223	0	w/40 sxs cmt
PROD	5.5	3035	0	w/250 sxs cmt
SURF	8.625	493	0	w/210 sxs cmt

\$106.60

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2007 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-8356

Proposed Ordered 400 sxs 60/40 pozmix - 10% gel - 1000# hulls.
Plugging Perf Tech set CIBP at 2950' - shot a two hole perf at 1550'.
Method: 4 1/2" liner was from 3013' to 3223'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/05/2007 1:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2900'. Rigged to tubing - pumped 40 sxs 60/40 pozmix, followed with 60 sxs cement with 300# hulls mixed in.
Pulled tubing to 1600'. Rigged to tubing - pumped 40 sxs 60/40 pozmix, followed with 60 sxs 60/40 pozmix with 200# hulls mixed in to circulate cement into pit.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 20 sxs cement.
Max. P.S.I. 450#. S.I.P. 400#.
Rigged to 8 5/8" casing - pumped 130 sxs 60/40 pozmix with 200# hulls.
Max. P.S.I. 450#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
2980	2990		
2800	2810		

INVOICED
DATE 3-8-07
INV. NO. 2007061441

Remarks: ALLIED CEMENTING COMPANY-TICKET #33081.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 07 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

MAR 06 2007

PKT