

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 9-44

LOCATION SW/4SW NW

SEC. 27 TWP. 9 RGE. 18

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease ^{KCC 2A} William Mc Monchie

Operator Stanolind Oil & Gas Address Gorham, Kans

Field _____ County Rooks

Total Depth 5592 Feet.

Plugging Contractor Halliburton Co

Plugging Contractor's License No. _____

Address _____

(Describe briefly the manner in which the well was plugged)

15' at 148' circulated with cement - 5 1/2' at 5589' with
200 sax cement behind on bottom - D.V. tool at 1440' with
400 sax cement 1440' to 0'. Cement and Baker plugs to 5390' -
Perforations at 5382'.

Pumped hole full commercial mud (40 sax), pumped cementing plug
to 555' followed by 45 sax cement - cement 555' to 0'.

Mudding and cementing by Halliburton Co - No pipe recovery.

Received
2/12/54

J. Edward Kelly
District Conservation Agent

Date 2-9-54

PLUGGING
FILE SEC 27 T 9 R 18W
BOOK PAGE 9 LINE 44