

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 13 1973  
8-13-73  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center, Wichita, Kansas 67202

Lease Name Bedard Well No. 1

Location SE NW NW Sec. 18 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3523'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 10:15 A Day 11 Month 8 Year 1973

The above well was plugged as follows:

Total Depth 3523' 8 5/8 csg (Unknown)

5 1/2 csg set at 3519' cw 125 sk cmt.

5 1/2 csg PBD 3500' with top perf. 3249'.

Set 5 1/2 wood plug at 3000'--poured 10' sd--dumped 5 sk cmt W/dump bailer. (2950-3000)

Cutoff and recovered 2490' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls--70 sk cmt--10 sk gel

& water--released 8 5/8 plug & pumped 50 sk cmt by Allied Cementing Co.

Max. PP 500 lbs. SIP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey  
Well Plugging Supervisor

INVOICED

DATE 8/15/73

INV. NO. 7761-W