

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 62-8
LOCATION SE NWSE Ka
~~NE SE SE~~
SEC. 28 TWP. 9 RGE. 18

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. B-1 Lease Widman *Box 757*
Operator Cities Service Oil Address Great Bend, Kans
Field _____ County Rooks
Total Depth 3610 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 316' circulated with cement - 5 1/2" at 3592 with
200 sax cement behind. Cement drilled out to 3587' T. D.
Perforations at 3387'.
Filled with sand and chat to 3375', set 4 sax cement with
dump bailer, pulled 2560' 5 1/2", filled with mud to 300', set
rock and 15 sax cement, filled with mud to 35', set rock
bridge and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
4/18/51
APR 18 1951

PLUGGING
FILE SEC 28 T 9 R 1801
BOOK PAGE 687 LINE 8

CONSERVATION DIVISION
Wichita, Kansas

John J. ...
District Conservation Agent

Date 4-15-51