

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-26-60
SEP 26 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: SE NE NW Sec. 18 Twp. 9 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3553

I have this date completed supervision of plugging of:

Lease Name: Bedard Well No. 1

Operator's Full Name: Robinowitz Oil Co

Complete Address: Box 7027 Tulsa, Okla

Plugging Contractor: A. L. Jackson Dng Co

Address: Great Bend, Kans License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 9AM Day 20 Month 9 Year 60

The above well was plugged as follows:

10 3/4 212' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 550', displaced
20 sax cement through drill pipe at 550', heavy mud to 180', set
cementing plug and 20 sax cement at 180', heavy mud to 30', set
cementing plug, 1 sack hulls and 10 sax cement to bottom cellar.

Signed: Jewel Ogden
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 9/29/60
INV. NO. 1963-W