

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSION  
3/26/63  
MAR 26 1963CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Lease Name Baldwin Well No. 1

Location NE NE NW Sec. 28 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3602

Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 6PM Day 22 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 1510' circulated with cement - 5 1/2" 3598' with 150 sax cement

Filled with sand to 3580', set 4 sax cement with dump bailer - pulled

2660' 5 1/2" to 500', circulated hole with heavy mud ( 18 sax Gel ), displaced

20 sax cement through 5 1/2" at 500', heavy mud to 190', displaced 20 sax

cement through 5 1/2" at 190', heavy mud to 35', set bridge and cement to

bottom cellar.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Eldon Peety

Well Plugging Supervisor

DATE 3/26/63INV. NO. 6994-W