

f

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION
MAY 30 1978
5-30-78
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-163-20,797-00-00 (of this well)

Operator's Full Name Martin Explorations
Complete Address 527 Union Center, Wichita, Kansas
Lease Name Baumgartner Well No. 1
Location N/2 SW SE Sec. 20 Twp. 9 Rge. (E) (W) 18
County Rooks Total Depth 3620'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Murfin Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 7:35 A Day 23 Month 5 Year 1978

The above well was plugged as follows:

RTD 3620' 8 5/8 csg set 209' cwc 150 sk. Flg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.
Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6-1-78
INV. NO. 7406.4

Signed: Leo Massey
Well Plugging Supervisor