

AP

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1970
4-16-70
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Oil Property Management, Inc.
Complete Address 300 Insurance Bldg., Wichita, Kansas 67202
Lease Name John "B" Well No. 1
Location SW SW SW Sec. 20 Twp. 9 Rge. (E) (W) 18
County Rooks Total Depth 3606
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 12N Day 13 Month 4 Year 1970

The above well was plugged as follows:

Total Depth 3606' 8 5/8 csg set at 172' cwc
5 1/2 csg set at 3606' cw 125 sk cmt.
5 1/2 csg top perf. (3564)
5 1/2 csg squeezed thru Dakato section. No pipe recovered.
Pumped thru 5 1/2 plug container with 30 sk cmt—35 sk gel W/5 sk hulls—plug and 70 sk cmt.
Pumped down amulus (8 5/8—5 1/2) with 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Brock Massey
Well Plugging Supervisor

DATE 4/16/70
INV. NO. 1730-W