

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: LACHENMAYR OIL., LLC
Address: 904 EMMALINE AVE. NEWTON, KS 67114
Phone: (316) 282-0400 Operator License #: 6804
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12/17/2006 (Date)
by: DAVE WERTZ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
VIOLA Depth to Top: 3371 Bottom: 3389 T.D. 3389
HUNTON Depth to Top: 3366 Bottom: 3368 T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-173-20841-00-00
Lease Name: SHAWVER-WRIGHT
Well Number: L-1
Spot Location (QQQQ): W/2 - NW - NW -
4620 Feet from North / South Section Line
4880 Feet from East / West Section Line
Sec. 7 Twp. 26 S. R. 1 East West
County: SEDGWICK
Date Well Completed: 12/06/1989
Plugging Commenced: 12/28/2006
Plugging Completed: 01/10/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		SURFACE	221'	8 5/8"	221'	0
		PRODUCTION	3389	5 1/2"	3389	1565'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SANDED BACK TO 3305', DUMPED 5 SKS CEMENT ON TOP OF SAND WITH DUMP BAILER. DUG OUT CELLAR. SETUP JACKS

PULLED SLIPS. WORKED PIPE, SHOT OFF @ 1565'. LAYED OUT PIPE.

RUN 1" INSIDE 8 5/8' FROM SURFACE TO 275'. PUMPED 117 SKS CEMENT DOWN 1', FILLED TO SURFACE

PULLED OUT 1", TOPPED OFF WITH CEMENT

Name of Plugging Contractor: B. P. C. WELL PLUGGING License #: 32475

Address: P. O. BOX 282, BURDEN, KS 67019

Name of Party Responsible for Plugging Fees: HOWARD LACHENMAYR

State of KANSAS County, HARVEY, ss.

Howard Lachenmayr


(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Howard Lachenmayr
(Address) 904 Emmaline Newton KS 67114

SUBSCRIBED and SWORN TO before me this 8th day of March, 2007
Barbara L. Brown My Commission Expires: 10-11-10
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



PKT