

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Southern Star Central Gas Pipeline
Address: 4700 Highway 56 Owensboro, Kentucky 42304
Phone: (270) 852-4490 Operator License #: 33097
Type of Well: Gas Storage Observation Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9/27/2006 (Date)
by: Steve Korf (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Squirrel Sandstone Depth to Top: 770' Bottom: 833' T.D. 1010'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 003-19438-00-01
Lease Name: North Welda Gas Storage Field
Well Number: 0-87
Spot Location (QQQQ): _____ - SE - NE - SW
1977 Feet from ☐ North / ☒ South Section Line
2847 Feet from ☒ East / ☐ West Section Line
Sec. 27 Twp. 21 S. R. 19 ☒ East ☐ West
County: Anderson
Date Well Completed: 3-25-1936
Plugging Commenced: 9-28-2006
Plugging Completed: 9-28-2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Squirrel Ss.	gas	0	25'	12.75"		
		0	855'	4.5"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2" with stinger inside 4.5" to 746'. Stung through retainer plug, pumped 30 sks. cement at 500#.

Pulled stinger out and pumped cement to surface, pulled tubing and topped well off.

Total cement 330 sks. Class A

Cut casing 4' below surface and reclaimed area.

Name of Plugging Contractor: Splane Pulling & Roustabout Service License #: 6372

Address: P.O. Box 386 Chanute, Kansas 66720

Name of Party Responsible for Plugging Fees: Southern Star Central Gas Pipeline

State of Kentucky County, Daviess, ss.

D. Mark Rouse Staff Geologist

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) D. Mark Rouse

(Address) SSCGP 4700 Hwy. 56 Owensboro, Kentucky 42304

SUBSCRIBED and SWORN TO before me this 10th day of November, 2006

Shelly A. Bru My Commission Expires: 10-30-2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KCC DISTRICT #3

NOV 20 2006

RECEIVED, KS
KANSAS CORPORATION COMMISSION

DEC 22 2006

CONSERVATION DIVISION
WICHITA, KS

PPT