

\$35.00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER 15-003-19436-00-01

SWSWSE Sec/Twp/Rge 34-21S-19E

487 feet from south section line

2492 feet from east section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 33097

Lease/Well# NORTH WELDA 0-72 *Gas Storage Field*

County ANDERSON

Operator: SOUTHERN STAR CENTRAL....

Well Total Depth 715 feet

Name &amp; 4700 HIGHWAY 56

Production Pipe: 7 Size Feet 715

Address OWENSBORO, KENTUCKY 42301

Surface Casing: UNK Size Feet UNK

AB oil well Gas Well X SWD Well/ Input Well

D &amp; A

Other well as hereinafter indicated:

GAS STORAGE OBSERVATION WELL

Plugging Contractor: HURRICANE WELL SERVICE, INC.

Lic. #

30776

Address: PO BOX 78228 WICHITA, KS. 67278-2228

Company to plug at: Hour: Day: 30 Month: AUGUST 2006

Plugging proposal received from: SOUTHERN STAR

Company Name: Phone: 270-852-4490

Were: PULL TUBING AND PACKER. FILL WELL WITH CEMENT, TD TO SURFACE.

Plugging Proposal Received by:

FRANK GUILFOYLE

Plugging attended by Agent: All X Part

TECHNICIAN

None

Operations Completed: Hour: Day: 30 Month: AUGUST 2006

Actual Plugging Report: PULL 4 1/2" TUBING AND PACKER FROM WELL. RUN 2" TUBING TO

714 FT. PUMP CEMENT WITH 2% GEL FROM TD TO SURFACE. PULL TUBING AND TOP OFF WELL.

HOOK ONTO 7" AND SQUEEZE 25 SACKS INTO FORMATION AND SHUT IN WITH 300 PSI. WELL

PLUGGED. TOTAL OF 180 SACKS OF CEMENT.

RECEIVED

KANSAS CORPORATION COMMISSION

INVOICED

DEC 22 2006

DATE 3-12-07

CONSERVATION DIVISION

WICHITA, KS

Remarks: OPERATER PLUGGED WELL.

INV. NO. 2007001448

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

  
 TECHNICIAN

