



STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: ~~15-185-10438-00-00~~ **15-185-22506-00-00**
 Spot: ~~SEWNE~~ **NWNE** Sec/Twnshp/Rge: 22-24S-13W
~~4290~~ **4620** feet from S Section Line, ~~1650~~ feet from E Section Line
 Lease Name: KELLER KAY **1980** Well #: ~~2~~ **4**
 County: STAFFORD Total Vertical Depth: 4110 feet

Operator License No.: 3182
 Op Name: N P F ENERGY CORPORATION
 Address: PO BOX 3827
TUSTIN, CA 92781

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4108	2127	NO INFO
SURF	8.625	328		NO INFO

\$ 133.58

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2007 9:00 AM
 Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
 Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3660' & 5 SX CMT. PLUG AT 780' WITH 15 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 35 SX CMT.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 02/28/2007 10:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:
 SANDED TO 3660' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 780' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3809	3817		
3791	3801		
3716	3724		

RECEIVED
 KANSAS CORPORATION COMMISSION
 MAR 09 2007
 CONSERVATION DIVISION
 WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.
 Plugged through: CSG

INVOICED

DATE 3-13-07
 INV. NO. 2007061457

District: 01

RECEIVED

MAR - 2 2007

KCC Dodge City

Signed Richard M. Lacey
 (TECHNICIAN)

Form CP-2/3

8

RST