

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-16601-00-01
Spot: SENWSE Sec/Twnshp/Rge: 28-18S-15W
1338 feet from S Section Line, 1409 feet from E Section Line
Lease Name: BIRD A OWWO Well #: 1
County: BARTON Total Vertical Depth: 3535 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: P.O. BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3466	0	w/unknown sxs cmt
SURF	8.625	908	0	250 SX CMT. \$ 114.89

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/09/2007 9:00 AM
Plug Co. License No.: 5364 Plug Co. Name: BEREN CORPORATION
Proposal Rcvd. from: MARK LEIKER Company: BEREN CORPORATION Phone: (785) 628-6101

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2007 3:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perf at 900' and 400'.
Ran tubing to 2800' - pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled to 1900' - circulated with 125 sxs cement with 100# hulls.
POOH. Pumped 50 sxs cement down backside.
Max. P.S.I. 200#. S.I.P. 100#.
Tied onto casing - pumped 100 sxs cement.
Max. P.S.I. 600#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
1798	1799		75 SX
1773	1783		
1772	1786		65 SX

INVOICED

DATE 3-15-07
INV. NO. 2007061403

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

16.

Signed *Case Morris*
(TECHNICIAN)

RECEIVED

MAR 12 2007 Form CP-2/3

KCC WICHITA

MAR 06 2007

PKT

BEREN CORP.
970 4TH FINANCIAL CENTER
WICHITA, KS.

#1 BIRD "A"

28-18-15W
C SE/4

CONTR CO. TOOLS

CTY BARTON

GEOL _____

FIELD OITS-ALBERT

E 1912 KB CM 5/15/76 CARD ISSUED 10/7/76 IP SIGW
1773-83 OA

+	+
+	+
+	*

API

	TOPS	DEPTH	DATUM
ANH		908	+1004
DODGE		3150	-1238
LANS		3196	-1284
BKC		3420	-1508
CONG		3452	-1540
R SD		3464	-1552
TD		3513	-1601
PBTD		2400	- 488

OLD INFO: OPERATOR WAS SKELLY OIL CO.;
SPD 11/2/39, SET 8-5/8" 908; COMPLETED
AS 18,300MCFGPD/1/1/40
MICT - SG 3205-28, 2 1/2 MG @ 3467, 6MG @
3478

NEW INFO: PBTD 2400, SET 5 1/2" 1799/75SX,
MICT - CO, PF 1773-83 OA, FRAC 10,000#
SD + 10,000G GEL W, SWB LD & GA 171
MCFGPD, SIGW, SHALLOW FORMATION TOPS
TIGHT - TO BE RELEASED AT A LATER DATE

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS