

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-60012-00-01
Spot: SWNWNE Sec/Twnshp/Rge: 22-19S-11W
990 feet from N Section Line, 2310 feet from E Section Line
Lease Name: HIRSCH OWWO Well #: 2
County: BARTON Total Vertical Depth: 3372 feet

Operator License No.: 5310
Op Name: FOUR-WAY OPERATING, INC.
Address: PO BOX 698
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3358	0	150 SX
SURF	8.625	220	0	140 SX

\$109.59

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/07/2007 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2007 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded off bottom to 3280' and covered with 5 sxs cement using a dump bailer.
Cut 5 1/2" casing at 2300' - 2100' - 2028'. Parted and came loose.
03/08/2007 - 8:30AM
Cut casing at 2028' - pulled to 1335'.
Rigged to casing - pumped 95 sxs cement with 200# hulls mixed in.
Pulled casing to 620'. Rigged to casing - pumped 40 sxs cement with 100# hulls mixed in.
Pulled casing to 150'. Rigged to casing - pumped 40 sxs 60/40 pozmix.
Pulled rest of casing. Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3358	3372		

INVOICED
DATE 3-15-07
INV. NO. 2007061465

Remarks: COPELAND ACID & CEMENTING SERVICES-TICKET#C-031665.

Plugged through: CSG

District: 04

HP

Signed [Signature]
(TECHNICIAN)

MAR 08 2007

RECEIVED

Form CP-2/3

MAR 12 2007

KCC WICHITA

[Signature]

FOUR-WAY OPERATING, INC.
BOX 658, GREAT BEND, KS.

#2 HIRSCH "OWWO"

22-19-11W
SW NW NE

CONTR ROCKHOLD ENG., INC. CTY BARTON

GEOL FIELD LANTERMAN

E 1780 RB CM 1/23/75 CARD ISSUED 3/25/76 IP P 25 BOPD + TR WTR
ARB 3358-72

+	+	+
+	+	+
+	+	+

API	TOPS	DEPTH	DATUM
HEEB		2910	-1130
TOR		3028	-1248
LANS		3050	-1270
CO'B		3323	-1543
ARB		3352	-1572
TD		3359	-1579
DDTD		3372	-1592
Arch Top			+1238
Base			+1213

OLD INFO: OPERATOR WAS BIRMINGHAM-
BARTLETT DRG. CO. #1 HIRSCH; SPD 5/7/
50; SET 8" @ 220; COMPLETED AS D&A/
5/26/50
NO SHOWS

NEW INFO: RE-ENTERED 1/23/86; WASHED
DWN TO OTD 3359, SET 5 1/2" 3358, DD
3372, A 250, REC LD, RE-AC 500, REC LD,
SWB 1 1/2 BOPH + TR W, POP

INDEPENDENT OIL & GAS SI
WICHITA, KANSAS