

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22685-00-00

Spot: SWNESE

Sec/Twnshp/Rge: 16-16S-14W

1650 feet from S Section Line,

990 feet from E Section Line

Lease Name: STOSKOPF

Well #: 2

County: BARTON

Total Vertical Depth: 3411 feet

Operator License No.: 3134

Op Name: MORRIS, TERRY E. DBA G L M COMPA

Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3410	0	w/175 sxs cmt
SURF	8.625	329	0	w/200 sxs cmt

\$110.80

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/12/2007 9:00 AM

Plug Co. License No.: 31073

Plug Co. Name: MAIER WELL SERVICE, INC.

Proposal Rcvd. from: TOM MAIER

Company: GLM COMPANY

Phone: (785) 483-1307

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 02/12/2007 11:00 AM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Casing possibly parted in well - tried to get down with power swivel - not making any progress.
Ran tubing to 568' - circulated with 70 sxs 60/40 pozmix - 10% gel cement.
POOH. Tied onto casing - pumped 180 sxs cement.
Cement circulated up backside (outside surface pipe).
Max. P.S.I. 600#. S.I. P. 300#.

INVOICED
DATE 3-15-07
INV. NO. 2007061466

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

MD.

Signed

Case Morris

(TECHNICIAN)

RECEIVED

MAR 12 2007

Form CP-2/3

KCC WICHITA

MAR 06 2007

pet

PETX PETROLEUM CORP.
 1700 SECURITY LIFE BLDG.
 DENVER, CO 80202
 CONTR H-30, INC.

#2 STOSKOPF

16-16-14W
 SW NE SE

CTY BARTON

GEOL

FIELD NUSS SOUTH EXT (1/8 W)

1936 KB CM 2/24/82 CARD ISSUED 5/20/82 IP P 20 80 & 20 EWPD
 1931 GL LANS 3294-3335 OA
 API 15-009-22,685

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
HEEB		3079	-1143
TOR		3096	-1160
LANS		3149	-1213
BKC		3343	-1409
ARB		3405	-1469
LTD		3411	-1475
Awk			+ 1025

8 5/8" 329/200sx; 4 1/2" 3410/175sx
 DST (1) 3167-3191/45-60-45-60, 360'
 GIP, 25' CC GSY M, 60' HCC GSY
 M(20% M, 60% O & 20% G), SIP
 345-593#, FP 54-64/75-79#, HP
 1779-1768#
 DST (2) 3374-3423/45-45-45-45, REC
 300' MW, SIP 1080-1036#, FP 97-
 12/150-172#, HP 1908-1897#
 DST (3) 3283-3344/30-30-30-30, 120'
 GIP, 75' CCM, SIP 701-614#, FP
 43-53/64-75#, HP 1800-1790#

(OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS