

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-14806-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 15-18S-11W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: DREWS 'AP' Well #: 1
County: BARTON ^{KCC PER 3/15/07} _{PER 2/25/07} Total Vertical Depth: 3356 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3332	0	w/125 sxs cmt
SURF	8.625	228	0	w/unknown sxs cmt

\$109.07

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2007 2:15 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2007 4:15 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 1994' - circulated with 225 sxs 60/40 pozmix - 10% gel cement with 800# hulls.
POOH. Pumped 25 sxs cement down casing.
Max. P.S.I. 350#. S.I.P. 350#.
Well was squeezed at 405' with 150 sxs cement.

Perfs:

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

Case Morris

(TECHNICIAN)

INVOICED
DATE 3-15-07
INV. NO. 2007061468

RECEIVED

MAR 12 2007

KCC WICHITA

Form CP-2/3

MAR 07 2007

RET

15-009-14806-00-00

R L WILLIAMS #1 DREWS 15-18-11W
SW SW SW

Contr. _____ BARTON _____ County

E 1791 Comm. 7-31-46 Comp. 8-6-46 IP _____ 115 BOPD

Tops	Depth	Datum
ANEY	605	
BR LM	3018	
LANS	3037	
ARB	3331	
TD	3362	

Casing
8" 228
5" 3332

BL 1 b1r OPB: A/1500
no inc
A/750;
OWPB: 3250
Perf 15/3110-15
Flow 17 BOPH/5 hr

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS