

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01610-00-00
Spot: SENWSW Sec/Twnshp/Rge: 3-9S-19W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: ROSTOCIL B Well Number: 3
County: ROOKS Total Vertical Depth: 3444 feet

Operator License No.: 5552

Production Casing Size: 5.5 feet: 3441

Op Name: GORE OIL COMPANY

Surface Casing Size: 8.625 feet: 307

Address: PO BOX 2757 202 SOUTH ST. FRANCIS
WICHITA, KS 67201

\$111.93

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/13/2003 8:30 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE INC

Proposal Rcvd. from: GARY REH

Company: GORE OIL COMPANY

Phone: (308) 345-1597

Proposed Plugging Method: Ordered out 220 sxs Swift Multi-Density Cement & 75 sxs common - 2% cc - 700# hulls.
Fluid level 100' from surface. CIBP at 3412' with one sack cement on top.
Squeeze 05-1981 - 193' w/54 sxs.
Ran casing scraper to 1140' - out of casing (Red Bed).

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/13/2003 12:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1061' - never made it back to 1140'.
Swift pumped 75 sxs common - 2% cc.
Pulled tubing to 785'.
Swift pumped 175 sxs Multi-Density Cement with 700# hulls - circulated cement.
PTOH. Shut in one hour.
Topped off with 45 sxs Swift Multi-Density Cement - casing full at surface.
Hooked up to backside - instant 500# pressure.
Note: Emergency plug orders given while rig over hole.

RECEIVED
5/21/03
MAY 21 2003
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 5-22-03

INV. NO. 2003061512

Form CP-2/3

MAY 14 2003

3-9-19W 22
 SE NW SW

SOHIO PETROLEUM COMPANY #3 ROSTOCIL B

Contr. STRAIN DRILLING COMPANY ROOKS County

E 2012 Comm. 7-8-50 Comp. 8-18-50 IP 1329 BOPD & 18% WTR
 DRAW DOWN

Tops	Depth	Datum
TOP	2945	
HEEB	3152	
LANS	3190	-1178
ARB	3439	-1427
T.D.	3444	

Casing
 8" 307 DP 3444
 5" 3441 SWB 1 1/2 BOPH
 AGID 1000

NOVOTNY POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS