

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01605-00-00
Spot: S2NESW Sec/Twnshp/Rge: 3-9S-19W
1650 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: ROSTOCIL A Well Number: 3
County: ROOKS Total Vertical Depth: 3460 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: PO BOX 2757 202 SOUTH ST. FRANCIS
WICHITA, KS 67201

Production Casing Size: 5.5 feet: 3456
Surface Casing Size: 10.75 feet: 322

\$12.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/12/2003 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1597

Proposed Plugging Method: Ordered out 300 sxs Swift Multi-Density Cement with 500# hulls.
Fluid level 30' from surface. Casing parted at 1693'. Perfs 3115' - 3411'.
CIBP at 3440'. Squeeze 01-1954 - 300 sxs at 838' to surface.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/12/2003 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3040'.
Swift pumped 75 sxs Multi-Density Cement with 500# hulls.
Pulled tubing to 1660'.
Swift pumped 180 sxs Multi-Density Cement with 300# hulls - circulated cement.
PTOH. Topped off with 5 sxs - casing full.
Hooked up to backside - pumped 45 sxs cement.
Max. P.S.I. 175#. S.I.P. 100#.
Note: Emergency plug orders while rig over hole.

RECEIVED
5/21/03
MAY 21 2003
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 5-22-03

INV. NO. 2003061562

Form CP-2/3

MAY 14 2003

SOHIO PETROLEUM & PETROLEUM, INC. # 3 ROSTICAL

3-9-19W. 22
S2 NE SW

Contr. _____ ROOKS _____ County

E 2037 Comm. 5-17-50 Comp. 6-23-50 IP 3000 BOPD
DRAW DOWN

Tops	Depth	Datum
HEEB	3166	-1129
LANS	3208	-1171
ARB	3154	-1417
T.D.	3160	-1423

Casing
 10" 322 DP: 3160
 5" 3156 SWB 5 1/2 BOPH/7 HRS
 ACID 500

BARRY POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS