

RECEIVED
5/13/03
MAY 13 2003

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

KCC WICHITA

WELL PLUGGING APPLICATION FORM

15-163-01605 ~~000~~ (PLEASE TYPE FORM and File ONE Copy)

API # 5-17-50 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 6/03

WELL OPERATOR Gore Oil Company KCC LICENSE # 5552
(owner/company name) (operator's)

ADDRESS P.O. Box 2757 CITY Wichita

STATE KS ZIP CODE 67201-2757 CONTACT PHONE # (316) 263-3535

LEASE Rostocil A WELL# 3 SEC. 3 T. 9S R. 19 (East/West)

S/2-NE SW SPOT LOCATION/Q000 COUNTY Rooks

1650 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

3300 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 10 3/4" SET AT 322' CEMENTED WITH 175 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 3458' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3408-11; 3273-75'; 3267-69'; 3245-47'; 3206-13';

ELEVATION 2039' T.D. 3460' PBD 3435' ANHYDRITE DEPTH 1451' 3115-21'
(G.L. (K.B.)) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Run tubing to 3000', Pump 75 sx cement w/5 bags Hulls.

Pull 50 jts., Circulate cement to surface. Fill surface pipe as per Rick

Williams w/KCC.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Reh PHONE# () 308-345-1597

ADDRESS P.O. Box 878 City/State McCook, NE 69001

PLUGGING CONTRACTOR Swift Services, Inc. KCC LICENSE # 32382

ADDRESS P.O. Box 466, Ness City, KS (company name) PHONE # () 785-798-2300 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?): 5/12/03 8 a.m. plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5/12/03 AUTHORIZED OPERATOR/AGENT: _____

Larry M. Jack (signature)

15-163-01605-1000

SOHIO PETROLEUM COMPANY
Russell, Kansas

RECEIVED

MAY 13 2003

KCC WICHITA

Drillers Well Log

Rostocil No. "A" 3

C-S/2 NE SW Sec. 3-9S-19W
Russell, County, Kansas

Commenced RD 5/17/50
Completed RD 5/30/50
Total Depth 3460'

Elevation: ?
Initial Prod: ?
Contractor: Powell & Peters Drilling
Company, Inc.

Casing: 322' 10 3/4" 32.75# H 40 8rd thd. Smls.
3456' 5 1/2" 14# 8rd thd. Republic Elec. Weld.

| Strata | Depth |
|------------------|-------------|
| Surface Clay | 0 - 40 |
| Shale & Shells | 40 - 322 |
| Shale | 322 - 350 |
| Sand & Iron | 350 - 435 |
| Blue Sandy Shale | 435 - 895 |
| Anhydrite | 895 - 926 |
| Sand | 926 - 1180 |
| Sand & Shale | 1180 - 1260 |
| Red Rock, Sandy | 1260 - 1451 |
| Lime | 1451 - 1500 |
| Shale & Shells | 1500 - 1740 |
| Shale & Lime | 1740 - 1900 |
| Shale & Shells | 1900 - 2060 |
| Lime & Shale | 2060 - 2198 |
| Lime | 2198 - 2210 |
| Shale & Lime | 2210 - 2270 |
| Lime | 2270 - 2355 |
| Lime & Shale | 2355 - 2535 |
| Shale & Shells | 2535 - 2882 |
| Lime, Sandy | 2882 - 2892 |
| Lime | 2892 - 3458 |
| Arbuckle | 3458 - 3460 |

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

POWELL & PETERS DRILLING CO., INC.

By C. M. Powell
C. M. Powell Pres.

Signed and sworn to in my presence this 2nd day of June, 1950, by C. M. Powell, President of the POWELL & PETERS DRILLING CO., INC., a corporation in the State of Kansas.

Deeter Mier
Notary Public

My Commission Expires : September 29, 1951.