

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rooks County. Sec. 29 Twp. 9S Rge. (E) 18 (W)

Location as "NE/CNW%SW%" or footage from lines NE NW SE

Lease Owner Abercrombie Drilling, Inc.

Lease Name KOEHLER Well No. 1

Office Address 801 Union Center, Wichita, Ks. 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 12, 1971

Application for plugging filed (verbally) November 12, 1971

Application for plugging approved (verbally) November 12, 1971


Plugging commenced November 12, 1971

Plugging completed November 12, 1971

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3702 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug set at 720' w/60 sx.  
2nd plug set at 190' w/20 sx.  
Top plug set at 40' w/10 sx.  
Job completed at 8:30 a.m. 11-12-71.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 16 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 71

My commission expires February 10, 1975

Beverly Mann  
Beverly Mann  
Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	KOEHLER #1
LOCATION:	NE NW SE, Sec. 29-9S-18W Rooks County, Kansas
GEOLOGIST:	Jack K. Wharton
SPUD DATE:	November 5, 1971
COMPLETION DATE:	November 12, 1971

0	35	Clay
35	55	Sand
55	680	Shale
680	720	Sand
720	1065	Shale
1065	1260	Sand
1260	1537	Shale
1537	1580	Anhydrite
1580	1965	Shale
1965	2485	Shale & Lime
2485	3298	Lime & Shale
3298	3575	Lime
3575	3650	Lime & Shale
3650	3702	Lime
	3702	Rotary Total Depth

Drilled 210' of 12 1/4" surface hole. Set 8-5/8" surface csg. at 207' w/135 sx. cement. Cement circulated. Plug was down at 4:30 p.m. 11-5-71.  
Dry and Abandoned

ELECTRIC LOG TOPS

ELEVATION

Anhydrite	1541 (+ 636)
B/Anhydrite	1580 (+ 594)
Topeka	3123 (- 946)
Heebner	3334 (-1157)
Toronto	3355 (-1178)
Lansing	3378 (-1201)
B/K.C.	3585 (-1408)
Arbuckle	3661 (-1484)
ELTD	3703 (-1526)

2177 K.B.  
 2175 D.F.  
 2169 G.L.

RECEIVED  
 STATE CORPORATION COMMISSION  
 11/16/71  
 NOV 16 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS        )  
                               ) SS  
 COUNTY OF SEDGWICK    )

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KOEHLER #1, NE NW SE, Sec. 29-9S-18W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr  
 Jerry A. Langrehr  
 President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 15th day of November, 1971.

Beverly Mann  
 Beverly Mann Notary Public

My Commission Expires:

February 10, 1975