

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
10/18/76  
OCT 18 1976

CONSERVATION DIVISION  
WICHITA, KANSAS

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Oil Property Management, Inc.

Complete Address 300 Insurance Building, Wichita, Kansas 67202

Lease Name Baumgartner "A" Well No. 33

Location South Line NW NW Sec. 29 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3655'

Abandoned Oil Well XX Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated

Plugging Contractor Co. tools by Allied Cementing Co.

Address  License No.

Operation Completed: Hour 3:20 P Day 15 Month 10 Year 1976

The above well was plugged as follows:

Total Depth 3655' 8 5/8 csg set 156' cwc 100 sk.

5 1/2 csg set 3654' cw 100 sk cem.

5 1/2 csg PBTD 3626' & perf. (3600'-3609')

5 1/2 csg squeezed thru Dakato Section. No pipe recovered.

Allied Cementing Co. mixed & pumped down annulus with 50 sk 60-40 poz cem & shutin.

Down 5 1/2 csg with 50 sk 60-40 poz cem, -displaced with 35 sk gel & water W/500 lbs

hulls -released 5 1/2 plug & 75 sk 60-40 poz cem & shutin. FPP 450 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey  
Well Plugging Supervisor

INVOICE

DATE 10-18-76

WV. NO. 4004-W