

15-163-03025-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 07-10

LOCATION SW SE NW

SEC. 3 TWP. 9 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Navotny

Operator Continental Oil Co Address Box 481 Great Bend, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3509 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 240' circulated with cement - 6" at 3463' with

300 sax cement behind - P.B. to 3450' - perforations at 3400'

Filled with sand to 3390', set 5 sax cement with dump bailer,

pulled 2088' 6" casing, filled with mud to 240', set rock and

20 sax cement, mud to 30', set rock and 10 sax cement to bottom

cellar.

**PLUGGING**  
FILE SEC. 3 T 9 R 19W  
BOOK PAGE 67 LINE 10

RECEIVED  
STATE CORPORATION COMMISSION  
1724/53  
JAN 24 1953

CONSERVATION DIVISION  
Wichita, Kansas

*Edward J. Kelly*  
District Conservation Agent

Date 1-15-53