

15-163-02767-00-01

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 141-22

LOCATION NE-NE-SE

SEC. 3 TWP. 9 RGE. 19-W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease L. Rostock - Rostock

Operator Continental Oil Co Address R.F.D. #4 - Lyons - Kansas

Field Barry County Booker

Total Depth 3487 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 240 ft cemented all around  
6" casing set at 3477 & cemented with 240 sacks cement  
Well had been plugged back to 3450 ft with cement  
& tested. Perforated from 3396 to 3404 ft. Put in Plug  
in 6" casing above Perforations & 4 sacks of cement  
with Dump Bailey. Took out 1500 ft of 6" casing & filled  
hole with mud to 240 ft. Plug & 15 sacks of cement at 240 ft

Mud to within 20 ft of Surface  
& 10 Sacks of cement

C. N. Stough  
District Conservation Agent

Date 8-6-47

Jack. Shaw

Pipe Puller & Plugger

PLUGGING  
FILE SEC 3 T 9 R 19W  
BOOK PAGE 141 LINE 22

8-9-47