

15-163-01606-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
3/2/82  
MAR 2 1982

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION CONSERVATION DIVISION AGENT REPORT  
Wichita, Kansas

API Number 15- None

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Sohio Petroleum

Complete Address Box 30 Casper Wyoming 82602

Lease Name Rotocil 'A' Well No. 4

Location C52-SE-SW Sec. 3 Twp. 9 Rge. 19 (East)(West)

County Roos Total Depth 3441

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sohio Petroleum

Address Box 30 Casper Wyoming 82602 License No. \_\_\_\_\_

Operation Completed: Hour: 5:00 P Day: 24 Month: 2 Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8 set @ 314' w/175 sb - 5 1/2" set @ 3437' w/150 - plug @ 3400 -  
Paper set above 3194' @ 3100 - Rods parted @ 1500' - 2 1/2" casing parted  
@ 1288' balance of rods + tubing not recovered - hole in 5 1/2 @ 1100'  
Ordered 6 hullo + 350 sb cmt 50/50 polymer 6% gel 3% cc -> pumped  
in 2 hullo + 125 sb in annulus pressure to 500 PSI - shut in ->  
pumped in 4 hullo + 225 sb in 5 1/2 -> no pressure - wait 4 hrs  
Ordered 6 hullo 150 50/50 polymer 6% gel 3% CACL w 1/2 bb floccule -  
After 4 hr wait - pumped in 2 hullo + 50 cmt - pressure 600 PSI - wait 10 min  
pressure held - check annulus pressure ok - cmt by Wallburton  
Amount of Surface Casing: 314'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Howell  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICED

DATE 3-4-82  
INV NO. 9551-N

15-163-01606-00-00

RECEIVED  
STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

OCT - 1 1981

SOHIO PETROLEUM COMPANY  
Russell, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Drillers Well Log

Rostocil No. "A" 4

CS/2 SE SW Sec. 3-9S-19W  
Russell County, Kansas

Commenced RD: 5/31/50  
Completed RD: 6/10/50  
Total Depth 3438'

Elevation : ?  
Initial Prod: ?  
Contractor : Powell & Peters Drlg.  
Company, Inc.

Casing: 314', 8 5/8" 8rd thd.  
3437' 5 1/2" 8rd thd.

Strata	Depth
Clay	0 - 50
Shale & Shells	50 - 314
Shale & Sand	314 - 690
Redbed, Sandy	690 - 720
Shale & Shells	720 - 910
Sand	910 - 1085
Redbed	1085 - 1429
Anhydrite	1429 - 1467
Shale	1467 - 1535
Redrock & Shells	1535 - 1770
Shale & Shells	1770 - 1830
Broken Lime	1830 - 1945
Lime & Shale	1945 - 2105
Lime	2105 - 2699
Shale & Shells	2699 - 2940
Lime	2940 - 3438

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

POWELL & PETERS DRILLING CO., INC.

By C. M. Powell  
C. M. Powell Pres.

Signed and sworn to in my presence this 14th day of June, 1950, by C. M. Powell, President of the POWELL & PETERS DRILLING CO., INC., a corporation in the State of Kansas.

Isabel Obee  
Notary Public

My Commission Expires: 11-25-51