

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM - AMENDED
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

Operator: License # 33152
Name: Shawnee Oil and Gas, LLC
Address: 1900 Shawnee Mission Pkwy **RECEIVED**
City/State/Zip: Mission Woods, KS 66205
Purchaser: _____ **FEB 18 2004**
Operator Contact Person: Jeff Mohajir **KCC WICHITA**
Phone: (816) 748-3987
Contractor: Name: Layne Christensen Canada, Ltd.
License: 32999
Wellsite Geologist: Larry Weis

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>July 29, 2002</u>	<u>July 30, 2002</u>	<u>May 7, 2003</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 125-30132-00-00
County: Montgomery
SW-SW- _____ Sec. 32 Twp. 31 S. R. 15 East West
650 feet from **(S)** / N (circle one) Line of Section
933 feet from E / **(W)** (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW **(SW)**
Lease Name: W. Chism Well #: 13-32

Field Name: Jefferson-Sycamore
Producing Formation: Cherokee Coals
Elevation: Ground: 803 Kelly Bushing: 806
Total Depth: 1305 Plug Back Total Depth: 1304
Amount of Surface Pipe Set and Cemented at 21 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 1304 TD
feet depth to Surface w/ 150 sx cmt.
Alt II W/ M 2-6-07

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content N/A ppm Fluid volume _____ bbls
Dewatering method used N/A - Air Drilled
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____


INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: _____
Title: Agent Date: 2-16-04

Subscribed and sworn to before me this 16th day of February, 2004.

Notary Public: Melissa Thieme
Date Commission Expires: 6/20/05



KCC Office Use ONLY

Letter of Confidentiality Attached

If Denied, Yes Date: _____

Wireline Log Received

Geologist Report Received

UIC Distribution

✓

X

Operator Name: Shawnee Oil and Gas, LLC Lease Name: W. Chism Well #: 13-32
 Sec. 32 Twp. 31 S. R. 15 East West County: Montgomery

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No
 Electric Log Run Yes No
 (Submit Copy)
 List All E. Logs Run:
 Compensated Density Neutron
 Dual Induction

RECEIVED
FEB 18 2004
KCC WICHITA

✓ Log	Formation (Top), Depth and Datum	Sample
Name	Top	Datum
Pawnee Lime	701 KB	105
Excello Shale	841 KB	-35
V Shale	889 KB	-83
Weir - Pitt Coal	1012 KB	-206
Mississippian	1231 KB	-425

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8.65	23	21	Portland	8	
Casing	7 7/8	5.5	15.5	1305	Diacel	150	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	1013-1016.5	500 g 20% HCl/RWR-5 acid + 24 B KCl water + 263 B gelled water + 2268# 20/40	1013

TUBING RECORD		Size	Set At	Packer At	Liner Run	Yes	✓ No
		2.875	1092	1018			
Date of First, Resumed Production, SWD or Enhr.		Producing Method					
9/4/03		Flowing		✓ Pumping		Gas Lift Other (Explain)	
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity		
		8	13				

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-18.)

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____

Shawnee Oil & Gas, L.L.C.

1900 Shawnee Mission Parkway • Mission Woods, Kansas 66205 • (913) 362-0510 • Fax: (913) 362-0133

February 11, 2004

RECEIVED

FEB 18 2004

KCC WICHITA

Kansas Corporation Commission
Oil & Gas Conservation Division
130 S. Market, Room 2078
Wichita, KS 67202

ATTN: Ms. Sharon Ahtone

Re: W. Chism #13-32

Dear Ms. Ahtone:

I have enclosed the amended ACO-1 form and associated data for the following well:

API # 15-125-30132
W. Chism #13-32

We respectfully request that all information submitted be kept confidential and per provision E-4 of K.A. R. 82-3-107, we request that the term of the confidentiality be extended by one year.

If you need additional information or have any questions or comments, please contact me at (913) 748-3987.

Best regards,



Patrick Morgan, P.G.
Geologist

Enclosure

Cc Steve Crooke
Well File
GLNA

Rec'd
1-9-03
conf. 9-29-02
out 9-29-04