

TIGHT

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM

CONFIDENTIAL

ORIGINAL

WELL HISTORY, DESCRIPTION OF WELL & LEASE

Operator: License # 32309
Name: Presco Western, LLC
Address: 1775 Sherman Street, Suite 2950
City/State/Zip: Denver, CO 80203
Purchaser: Plains Marketing
Operator Contact Person: Richard J. Gray
Phone: (303) 864-1881, ext. 103
Contractor: Name: Val Energy
License: 5822

API No. 15 - 081-21495-0000
County: Haskell
SW SW SE Sec. 19 Twp. 30 S. R. 33 East West
330 feet from S / N (circle one) Line of Section
2310 feet from E / W (circle one) Line of Section

RECEIVED
JAN 14 2004
KCC WICHITA

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: McKinley Well #: 1-1519
Field Name: Lemon Victory

Wellsite Geologist: N/A
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abn.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

Producing Formation: Lansing
Elevation: Ground: 2962.5' Kelly Bushing: 2971.5'
Total Depth: 5100' Plug Back Total Depth: 4554'

KCC
JAN 12 2004
CONFIDENTIAL

Amount of Surface Pipe Set and Cemented at 1593 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set 3100 Feet
If Alternate II completion, cement circulated from _____
feet depth to ALT I W/ 12-28-06 w/ _____ sx cmt.

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content 1500 ppm Fluid volume 1800 bbls
Dewatering method used Dried and Filled

10/13/03 10/23/03 12/11/03
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

Location of fluid disposal if hauled offsite:
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: _____
Title: President Date: 1/12/04

Subscribed and sworn to before me this 12th day of January, 2004.

Notary Public: Jesse R. B. B.
Date Commission Expires: 11-9-04

KCC Office Use ONLY
 Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

✓

X

CONFIDENTIAL

Side Two

TIGHT ORIGINAL

Operator Name: Presco Western, LLC Lease Name: McKinley Well #: 1-1519
Sec. 19 Twp. 30 S. R. 33 East West County: Haskell

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken - (Attach Additional Sheets)
Samples Sent to Geological Survey
Cores Taken
Electric Log Run (Submit Copy)
List All E. Logs Run:

Log Formation (Top), Depth and Datum Sample
Name Top Datum
Lansing 4139'
Kansas City 4587'
Marmaton 4764'
Pawnee 4881'
Fort Scott 4919'

RECEIVED
JAN 14 2004
KCC WICHITA

KCC
JAN 12 2004
CONFIDENTIAL

CASING RECORD table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (In O.D.), Weight Lbs./ Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives. Includes Surface and Production rows.

ADDITIONAL CEMENTING / SQUEEZE RECORD table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives. Includes 3087'-port collar row.

PERFORATION RECORD - Bridge Plugs Set/Type table with columns: Shots Per Foot, Specify Footage of Each Interval Perforated, Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used), Depth. Includes 4 shots and CIBP set at 4554'.

TUBING RECORD table with columns: Size, Set At, Packer At, Liner Run. Includes 2 3/8" 5000' 5000'.

Disposition of Gas METHOD OF COMPLETION Production Interval
Vented Sold Used on Lease Open Hole Perf. Dually Comp. Commingled 4146-4172'
Other (Specify)

ALLIED CEMENTING CO., INC. 11166

CONFIDENTIAL

KCC

ORIGINAL

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT

Oakley

JAN 12 2004

DATE <u>10/15/03</u>	SEC. <u>19</u>	TWP. <u>30s</u>	RANGE <u>33w</u>	CALLED OUT <u>CONFIDENTIAL</u>	ON LOCATION <u>AB: 4:50 AM</u>	JOB START <u>8:15 AM</u>	JOB FINISH <u>9:30 PM</u>
LEASE <u>McKinley</u>	WELL # <u>1-1519</u>	LOCATION <u>Satanta 1 3/4 S 1/2 E N15</u>			COUNTY <u>Haskell</u>	STATE <u>Ks</u>	
OLD OR <u>(NEW)</u> (Circle one)							

CONTRACTOR Val Energy Rig #1
 TYPE OF JOB CMT 8 3/8 Surface Csg
 HOLE SIZE 12 1/4 T.D. 1593
 CASING SIZE 8 3/8 24# DEPTH 1593
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 900 MINIMUM 100
 MEAS. LINE _____ SHOE JOINT 44
 CEMENT LEFT IN CSG. 44
 PERFS. _____
 DISPLACEMENT 98.67 MBL

OWNER Same

CEMENT
 AMOUNT ORDERED
475 sks Lite + 39 cc 4# Flo-Seal
150 sks Com + 39 cc

COMMON	<u>150 sks @</u>	<u>8.35</u>	<u>1252.50</u>
POZMIX	_____ @ _____		
GEL	_____ @ _____		
CHLORIDE	<u>19 sks @</u>	<u>30.00</u>	<u>570.00</u>
<u>Lite weight</u>	<u>475 sks @</u>	<u>7.35</u>	<u>3491.25</u>
<u>Flo-seal</u>	<u>119# @</u>	<u>1.40</u>	<u>166.60</u>
	_____ @ _____		
	_____ @ _____		
	_____ @ _____		
HANDLING	<u>625 sks @</u>	<u>1.15</u>	<u>718.75</u>
MILEAGE	<u>54 / sk / mi</u>		<u>937.50</u>

RECEIVED
 JAN 14 2004
 TOTAL 7136.60

EQUIPMENT

PUMP TRUCK CEMENTER Max
 # 373-281 HELPER Dean
 BULK TRUCK
 # 361 DRIVER Jarrod
 BULK TRUCK
 # 218 DRIVER Larry

REMARKS:

KCC WICHITA

SERVICE

CMT 8 3/8 Surface Csg with 475 sks
Lite + 150 sks Com Drop Plug
Displace 99 MBL Land Plug
Flo-Set Cement Did Circulate

DEPTH OF JOB 1593
 PUMP TRUCK CHARGE 850.00
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 30 mi @ 3.50 105.00
 PLUG 8 3/8 Rubber @ 100.00

TOTAL 1055.00

CHARGE TO: Presco Western LLC
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

1-8 3/8 Guide Shoe @ 190.00
1-8 3/8 AFH Insert @ 242.00
3-8 3/8 Centralizers @ 33.00 99.00
1-8 3/8 Cement Basket @ 180.00

TOTAL 711.00

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Rodney Gonzalez

TAX _____
 TOTAL CHARGE 711.00
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME

ALLIED CEMENTING CO., INC.

14190

ORIGINAL

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

CONFIDENTIAL

SERVICE POINT

OAKLEY

DATE	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START	JOB FINISH
10-22-03	19	30S	33W		12:45 PM	8:15 PM	9:00 PM
LEASE	WELL #	LOCATION			COUNTY	STATE	
McKENKEY	1-1519	SATANTA 1 1/2 S - 1/2 E			HASKELL	KS	
OLD OR <u>NEW</u> (Circle one)					KCC JAN 12 2004		

CONTRACTOR VAL DRILL RIG #1
 TYPE OF JOB PRODUCTION STRING
 HOLE SIZE 7 7/8" T.D. 5100'
 CASING SIZE 4 1/2" DEPTH 5094'
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL PORT COLLAR DEPTH 3100'
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT 30'
 CEMENT LEFT IN CSG. 30'
 PERFS. _____
 DISPLACEMENT 78 1/2 BBL

OWNER SAME
 CEMENT CONFIDENTIAL
 AMOUNT ORDERED
225 SKS ASC 2% GEL 10% SALT
500 GAL WFR-2
~~ASC~~ 225 SKS @ 9 85/100 2216 25
 POZMIX @ _____
 GEL 4 SKS @ 10 00/100 40 00
 CHLORIDE @ _____
SALT 21 SKS @ 15 00/100 315 00
WFR-2 500 GAL. @ 1 00/100 500 00
 HANDLING 225 SKS @ 1 15/100 258 25
 MILEAGE 054 PER SK / MILE 337.50

EQUIPMENT
 PUMP TRUCK CEMENTER TERRY
 # 300 HELPER WAYNE MAX
 BULK TRUCK
 # 361 DRIVER LOWME
 BULK TRUCK
 # _____ DRIVER _____

RECEIVED
 JAN 14 2004
 SERVICE
 TOTAL 3667.50

REMARKS:

MIX 15 SKS RAT HOLS
MIX 500 GAL WFR-2 FOLLOWED BY
210 SKS ASC 2% GEL 10% SALT + DTS
PLACE WITH 78 1/2 BBL. WATER.
PLUG LANDED
FLOAT ~~WAS~~ DIDN'T HOLD.

KCC WICHITA
 DEPTH OF JOB 5094'
 PUMP TRUCK CHARGE 1130 00
 EXTRA FOOTAGE @ _____
 MILEAGE 30 MI @ 3 50/100 105 00
 PLUG @ _____ 39 00
 TOTAL 1273 00

THANK YOU

CHARGE TO: PRESCO WESTERN L.L.C.
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

4 1/2"
 1- GUESS SHOE @ 125 00
 1- AFU INSERT @ 210 00
 7- CENTRALIZERS @ 38 00 266 00
 1- BASKET @ 116 00
 1- PORT COLLAR @ 1400 00
 TOTAL 2117 00

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Robyn Gonzalez

PRINTED NAME

ALLIED CEMENTING CO., INC.

15268

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

CONFIDENTIAL

JAN 12 2004

ORIGINAL
SERVICE POINT:

Medicine L.D.G.

CONFIDENTIAL

DATE <u>10-28-03</u>	SEC <u>19</u>	TWP. <u>30S</u>	RANGE <u>33W</u>	CALLED OUT <u>3:00 AM.</u>	ON LOCATION <u>8:00 AM.</u>	JOB START <u>9:00 AM.</u>	JOB FINISH <u>10:00 AM.</u>
LEASE <u>Mck. 9/19</u>	WELL # <u>1-1519</u>	LOCATION <u>Satanita KS,</u>	COUNTY <u>Haskell</u>	STATE <u>KS</u>			
OLD OR <u>NEW</u> (Circle one)		<u>2S on 190 1/2 E Minto</u>					

CONTRACTOR Barker Line INC OWNER Presco-Western

TYPE OF JOB Port Collar

HOLE SIZE	T.D.
CASING SIZE <u>4 1/2</u>	DEPTH <u>3087</u>
TUBING SIZE <u>2 3/8</u>	DEPTH <u>3087</u>
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX <u>2000 PSI</u>	MINIMUM <u>-</u>
MEAS. LINE	SHOE JOINT

CEMENT
AMOUNT ORDERED 500x 60:40:8 + 1/4# Flo Seal

CEMENT LEFT IN CSG.
PERFS.

DISPLACEMENT Fresh Water 12 BBLs

COMMON	@		
POZMIX	@		
GEL	@		
CHLORIDE	@		
<u>Light weight # 500</u>	@	<u>7.75</u>	<u>3875.00</u>
<u>Flo Seal 125 #</u>	@	<u>1.40</u>	<u>175.00</u>
HANDLING	@		
<u>5.39</u>	@	<u>1.15</u>	<u>619.85</u>
MILEAGE			
<u>30 x 5.39 x .05</u>			<u>808.50</u>

EQUIPMENT

PUMP TRUCK	CEMENTER <u>David W.</u>
# <u>302</u>	HELPER <u>Dwayne W.</u>
BULK TRUCK	
# <u>363</u>	DRIVER <u>Larry C.</u>
BULK TRUCK	
#	DRIVER

RECEIVED

TOTAL 5478.35

JAN 14 2004

KCC WICHITA SERVICE

REMARKS:

PSI Tool To 1500 PSI open
Tool Pump 4 BBLs, min at 1400
PSI Mix 500x 60:40:8 + 1/4#
Flo Seal Displace w/ 12 BBLs
Fresh Water shut down run
Joint Pipe Reverses out w/ 15 BBLs
Washup Rig Down,

DEPTH OF JOB <u>3087</u>	
PUMP TRUCK CHARGE	<u>650.00</u>
EXTRA FOOTAGE	@
MILEAGE <u>30</u>	@ <u>3.50</u> <u>105.00</u>
PLUG	@
	@
	@

CHARGE TO: Presco Western
STREET _____
CITY _____ STATE _____ ZIP _____

TOTAL 755.00

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
TOTAL CHARGE ~~6225.00~~
DISCOUNT ~~6225.00~~ IF PAID IN 30 DAYS

SIGNATURE Rodney Gonzalez

Rodney Gonzalez
PRINTED NAME

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

CONFIDENTIAL

RECEIVED

JAN 14 2004

KCC WICHITA

LOG-TECH, INC.
1011 240th Ave.
HAYS, KANSAS 67601
(785) 625-3858

INVOICE ORIGINAL
11586

KCC

JAN 12 2004 Date 10-30-2003

CHARGE TO: Presco western LLC CONFIDENTIAL
ADDRESS _____

R/A SOURCE NO. _____ CUSTOMER ORDER NO. Verbal new

LEASE AND WELL NO. McKinley #1-1579 FIELD Lemon Victory

NEAREST TOWN _____ COUNTY Haskell STATE Ks

SPOT LOCATION 330' FEL + 2310' FEL SEC. 19 TWP. 30S RANGE 33W

ZERO 9' AGL CASING SIZE 4 1/2 WEIGHT _____

CUSTOMER'S T.D. _____ LOG TECH _____ FLUID LEVEL 96000

ENGINEER R Bollig OPERATOR M Webb

PERFORATING

Description	No. Shots	From	Depth To	Amount
<u>Perforate 13" HSC</u>	<u>36</u>	<u>4163</u>	<u>4172</u>	<u>1547.00</u>
	<u>16</u>	<u>4154</u>	<u>4158</u>	<u>452.00</u>
	<u>16</u>	<u>4150</u>	<u>4154</u>	<u>452.00</u>
	<u>16</u>	<u>4146</u>	<u>4150</u>	<u>452.00</u>
	<u>84</u>			

DEPTH AND OPERATIONS CHARGES

Description	From	Depth To	Total No. Ft.	Price Per Ft.	Amount
<u>Depth charge to set Plug</u>	<u>0</u>	<u>4554</u>	<u>4554</u>	<u>.16</u>	<u>728.64</u>
<u>gamma gun Run</u>	<u>0</u>	<u>4270</u>	<u>4270</u>	<u>.12</u>	<u>512.40</u>
<u>gamma gun Run</u>	<u>0</u>	<u>4270</u>	<u>4270</u>	<u>.12</u>	<u>512.40</u>
<u>gamma gun Run</u>	<u>0</u>	<u>4270</u>	<u>4270</u>	<u>.12</u>	<u>512.40</u>
<u>gamma gun Run</u>	<u>0</u>	<u>4270</u>	<u>4270</u>	<u>.12</u>	<u>512.40</u>

RECEIVED
1/12/04

PAID
1/12/04

MISCELLANEOUS

Description	Quantity	Amount
<u>Service Charge</u>		<u>450.00</u>
<u>11.00 4 1/2 Bolt Bridge Plug set @ 4554</u>		<u>650.00</u>
<u>RT 2.10 Pack off</u>		<u>100.00</u>

PRICES SUBJECT TO CORRECTION BY BILLING DEPARTMENT

RECEIVED THE ABOVE SERVICES ACCORDING TO THE TERMS AND CONDITIONS SPECIFIED ON THE REVERSE SIDE TO WHICH WE HEREBY AGREE.

Rodney Gonzales
Customer Signature Date 10-30-03

Sub Total	<u>6881.24</u>
Code Ref. Tool Insurance	
Tax	
IF PAID WITHIN 30 DAYS PAY DISCOUNT AMOUNT	<u>3780.00</u>