

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 095-20513-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____

Well Operator: CORAL PRODUCTION CORP. KCC License #: 32639

Address: 1600 STOUT ST.; SUITE 1500 City: DENVER

State: COLORADO Zip Code: 80202 Contact Phone: (303) 623 - 3573

Lease: ROHLMAN Well #: 1 Sec. 34 Twp. 28 S. R. 8 East West

Spot Location / QQQQ - C - SE County: KINGMAN

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 208' Cemented with: _____ Sacks

Production Casing Size: 4 1/2" Set at: 4137' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: PERFS: 4118'-4122' W/ 2 SHOTS/FT

Elevation: 1639' (G.L. / K.B.) T.D.: 4140' PBTD: 4137' Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): 50' SAND PLUG OVER PERFS @ 4118'-22'; 10 SKS ON TOP OF SAND; STRETCH CSG & SHOOT OFF; 30 SKS AT BASE OF SURFACE CSG, 1/2 IN, 1/2 OUT; 10 SKS @ SURFACE; CUT CSG 4' BELOW GRADE & WELD CAP

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? LOGS SENT WITH ACO-1 ON 3/22/05

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: JOE BORLA

FIELD ENGINEER Phone: (303) 601 - 5823

Address: P.O. BOX 188 City / State: POTTER, NE


Plugging Contractor: MID KAN WELL SERVICE, LLC KCC License #: _____ (Contractor's)

Address: P.O. BOX 326; RUSSELL, KS 67665 Phone: (785) 483 - 4400

Proposed Date and Hour of Plugging (if known?): APRIL 1, 2007

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/16/07 Authorized Operator / Agent: _____


(Signature)

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 19 2007

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KS

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Coral Production Corporation
1600 Stout Street, Suite 1500
Denver, CO 80202

March 20, 2007

Re: ROHLMAN #1
API 15-095-20513-00-01
SE 34-28S-8W, 1320 FSL 1320 FEL
KINGMAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



Barry Metz
Deputy Director

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000