

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 007-21201-00-61 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 11/8/89

Well Operator: WHITE PINE PETROLEUM CORP KCC License #: 5044
(Owner / Company Name) (Operator's)

Address: 110 S MAIN STE 500 City: WICHITA

State: KS Zip Code: 67202-3745 Contact Phone: (316) 262 - 5429

Lease: LUKENS Well #: 2 Sec. 28 Twp. 32 S. R. 11 East West

- SW - SE - NE Spot Location / QQQQ County: BARBER

2970 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 263 Cemented with: 300 Sacks

Production Casing Size: 5 1/2 Set at: 3803 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3618-23 DOUGLAS 15-50 600, 50-270
3570 + 5sks cement 15-40

Elevation: 1506 (G.L. / K.B.) T.D.: 3803 PBDT: 3714 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): AS KCC REQUIRES

15961 5sks 600, 5sks 270, 40' 15" pipe recovery 2870

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NOT AVAILABLE TO US

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: MIKE BRADLEY

Phone: (316) 262 - 5429

Address: 110 S MAIN STE 500 City / State: WICHITA KS 67202-3745

Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925

Address: 401 W MAIN LYONS KS 67554 Phone: (620) 727 - 3410
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): ASAP 3-7-07 - 12:30pm

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/8/07 Authorized Operator / Agent: William C Bradley
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202
Well already plugged - KCC-Dlg

RECEIVED
MAR 20 2007
KCC WICHITA

DIST
01

Quality Well Service, Inc.

401 West Main
Lyons, KS 67554

Invoice

Date	Invoice #
3/12/2007	855

Bill To
White Pine Petroleum Corp. 110 S. Main, Suite 500 Wichita, KS 67202-3745

P.O. No.	Terms	Lease Name
	net	Lukens 2

Description	Qty	Rate	Amount
Rig Time	21	175.00	3,675.00T
Rent on Floor		100.00	100.00T
Sand		35.00	35.00T
Cement	5	9.00	45.00T
Shots	1	150.00	150.00T
Torch		50.00	50.00T
Water Truck	5	70.00	350.00T
Backhoe	1.5	70.00	105.00T
Out of Town	2	120.00	240.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
3-5-07 Drove to location, raised pole, drove to motel.			
3-6-07 Drove to location, checked hole, sanded off bottom, loaded hole with water, dug cellar, unpacked casing head, set floor, checked hole, sand was at 3570', bailed 5 sacks cement with bailer, pulled slips, had 17" stretch, cut surface off 4' below ground, ripped casing at 2870', worked pipe, swedge in, left on tension, drove to motel.			
3-7-07 Drove to location, worked pipe free, pulled casing up to 600', pumped 15 gel, 50 sacks, pulled to 270', pumped 50 sacks, pulled to 40', circulated with 15 sacks, tore down floor and rig.			

Subtotal	\$4,805.00
Sales Tax (6.3%)	\$302.72
Total	\$5,107.72

RECEIVED

MAR 20 2007

KCC WICHITA

ALLIED CEMENTING CO., INC.

Federal Tax I.D.#

26167

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge

DATE <i>3-7-07</i>	SEC <i>28</i>	TWP <i>32S</i>	RANGE <i>11W</i>	CALLED OUT <i>3:00 PM</i>	ON LOCATION <i>11:45 AM</i>	JOB START <i>12:45 PM</i>	JOB FINISH <i>1:45 PM</i>
LEASE <i>LUKENS</i>	WELL # <i>2</i>	LOCATION <i>PELLEY, KS 1 SOUTH</i>		COUNTY <i>BARBER</i>	STATE <i>KANSAS</i>		
OLD OR NEW (Circle one)		<i>1/2 WEST, 1/2 SOUTH, 1/4 EAST</i>					

CONTRACTOR *QUALITY WELL SVC.* OWNER *WHITE PINE PETROLEUM*

TYPE OF JOB <i>OHP</i>	CEMENT
HOLE SIZE <i>7 7/8"</i>	AMOUNT ORDERED <i>15cy Gel</i>
CASING SIZE <i>8 5/8"</i>	<i>115cy 60:40:6</i>
TUBING SIZE <i>5 1/2"</i>	
DRILL PIPE	
TOOL	

PRES. MAX	MINIMUM	COMMON <i>A</i>	<i>69</i>	@	<i>10.65</i>	<i>734.85</i>
MEAS. LINE	SHOE JOINT	POZMIX	<i>46</i>	@	<i>5.80</i>	<i>266.80</i>
CEMENT LEFT IN CSG.		GEL	<i>21</i>	@	<i>16.65</i>	<i>349.65</i>
PERFS.		CHLORIDE		@		
DISPLACEMENT <i>8 1/2 Bbls. WATER</i>		ASC		@		

EQUIPMENT						
PUMP TRUCK # <i>414-302</i>	CEMENTER <i>KEVIN BRUNBAUM</i>					
	HELPER <i>DENNIS CUSHENBERY</i>					
BULK TRUCK # <i>389</i>	DRIVER <i>GREG RESELER</i>					
BULK TRUCK #	DRIVER					
		HANDLING	<i>136</i>	@	<i>1.90</i>	<i>258.40</i>
		MILEAGE	<i>136 - Medicine Lodge</i>			<i>240.00</i>
		TOTAL				<i>1849.70</i>

REMARKS:

Load Hole 15cy Gel
50cy - 600'
50cy - 270'
Calculate to surface @ 40'
with 15cy 60:40:6

CHARGE TO: *WHITE PINE PETROLEUM*
STREET _____
CITY *WICHITA* STATE *KANSAS* ZIP _____

SERVICE

DEPTH OF JOB	<i>600'</i>		
PUMP TRUCK CHARGE			<i>720.00</i>
EXTRA FOOTAGE		@	
MILEAGE	<i>7</i>	@	<i>6.00 42.00</i>
MANIFOLD		@	
		@	
TOTAL			<i>762.00</i>

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
ANY APPLICABLE TAX	@	
WILL BE CHARGED	@	
UPON INVOICING		
TOTAL		

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX	
TOTAL CHARGE	1849.70
DISCOUNT	1849.70 IF PAID IN 30 DAYS

SIGNATURE *[Signature]*

PRINTED NAME