

KANSAS CORPORATION COMMISSION
 OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
 Please TYPE Form and File ONE Copy

COPY

Form CP-1
 September 2003
 This Form must be Typed
 Form must be Signed
 All blanks must be Filled

API # 15 - 077-21,542 -00-0D (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date comp 4-11-06

Well Operator: Oil Producers Inc. of Kansas KCC License #: 8061
(Owner / Company Name) (Operator's)

Address: 1710 Waterfront Parkway City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: (316) 681 - 0231

Lease: Hendricks Unit Well #: 2-31 Sec. 31 Twp. 32 S. R. 9 East West

NW - NW - SW Spot Location / QQQQ County: Harper

2215 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

5080 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 309' Cemented with: 225 Sacks

Production Casing Size: 4 1/2", 10.5# and 11.6# Set at: 3764' Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3666'-3681'

Sand at 3610 + FSKS. pipe recovery 3020

Elevation: 1380' (G.L. / K.B.) T.D.: 3765' PBTD: 3731' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): as KCC requires

1400 35SKS 850 35SKS eir. 360. 90SKS

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Do not have

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Brandon Siroky

Phone: (316) 215 - 1357

Address: 1710 Waterfront Parkway City / State: Wichita, Kansas

Plugging Contractor: Quality Well Service KCC License #: 31925
(Company Name) (Contractor's)

Address: 401 W. Main - Lyons, Kansas 67554 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2-19-07 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

w - Allen

RECEIVED
 MAR 20 2007
 KCC WICHITA

Quality Well Service, Inc.

**401 West Main
Lyons, KS 67554**

Invoice

| | |
|-----------|-----------|
| Date | Invoice # |
| 3/12/2007 | 854 |

| |
|--|
| Bill To |
| Oil Producers Inc. of Kansas 1710 Waterfront Parkway Wichita, KS 67201 |

| | | |
|----------|-------|---------------------|
| P.O. No. | Terms | Lease Name |
| | net | Hendricks Unit 2-31 |

| Description | Qty | Rate | Amount |
|---|------|--------|-----------|
| Rig Time | 21.5 | 175.00 | 3,762.50T |
| Rent on Floor | | 100.00 | 100.00T |
| Sand | | 35.00 | 35.00T |
| Cement | 4 | 9.00 | 36.00T |
| Shots | | 150.00 | 150.00T |
| Torch | | 50.00 | 50.00T |
| Water Truck | 5.5 | 70.00 | 385.00T |
| Backhoe | 3.5 | 70.00 | 245.00T |
| Out of Town | | 120.00 | 120.00T |
| Phone Calls | | 15.00 | 15.00T |
| Clerical | | 20.00 | 20.00T |
| Wiping Rubber | | 50.00 | 50.00T |
| 3-1-07 Drove to location, backed rig in, drove to motel. | | | |
| 3-2-07 Drove to location, raised pole, checked hole, had bridge at 700', knocked bridge out, sanded off bottom, loaded hole with water, dug cellar, unpacked casing head, set floor, drove home. | | | |
| 3-5-07 Drove to location, checked hole, sand was at 3610', bailed 4 sacks cement with bailer, pulled slips, had 29" stretch, cut surface off 4' below ground, ripped casing at 3020', came free, pulled up to 1400', pumped 35 sacks, pulled up to 850', pumped 35 sacks, pulled up to 360', circulated with 90 sacks to surface, pulled rest of casing, tore down floor and rig, cleaned up location. | | | |

| | |
|-------------------------|------------|
| Subtotal | \$4,968.50 |
| Sales Tax (5.3%) | \$263.33 |
| Total | \$5,231.83 |

RECEIVED

MAR 20 2007

KCC WICHITA