

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 083-21468-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 10-19-00

Well Operator: Becker Oil Corporation KCC License #: 31093  
(Owner / Company Name) (Operator's)

Address: P. O. Box 1150 City: Ponca City

State: Oklahoma Zip Code: 74602 Contact Phone: ( 620 ) 287 - 4724

Lease: Shortridge Well #: 1 Sec. 5 Twp. 21 S. R. 21  East  West

NE - SE/4 - SE/4 Spot Location / QQQQ County: Hodgeman

960 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 227 Cemented with: 145 Sacks

Production Casing Size: 4 1/2 Set at: 2464 Cemented with: 450 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs 2423-35', CIBP at 2400', perfs 2343-54', 2309-22' and 2291-99'

Elevation: 2197 ( G.L. /  K.B.) T.D.: 2455 P.B.T.D.: 2400 Anhydrite Depth: 1355  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Mix 500# hulls with cement 60/40 pozmix, 6% gel, fill with cement from 2354' to surface and fill surface pipe with cement (total cement 150 sks +)

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Doug Brown

Phone: ( 620 ) 287 - 4724

Address: 2040 Milford Lane City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing KCC License #: \_\_\_\_\_  
(Company Name) (Contractor's)

Address: Great Bend, KS Phone: ( 620 ) 793 - 5861

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/16/07 Authorized Operator / Agent: *Doug M. Becker*  
(Signature)

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 21 2007  
CONSERVATION DIVISION  
WICHITA, KS

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Becker Oil Corporation  
PO Box 1150  
Ponca City, OK 74602-1150

March 21, 2007

Re: SHORTRIDGE #1  
API 15-083-21468-00-00  
NESESE 5-21S-21W, 960 FSL 330 FEL  
HODGEMAN COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely



Barry Metz  
Deputy Director