

4-042015

5-12

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-30,216-0000

SW N W SE *KCCAP*
~~SE NW SW~~ /4 SEC. 21, 09 S, 18 W
1650 feet from S section line
~~4290~~ 2310 feet from E section line

Operator license# 5030

Lease: Rempe Well # 4

Operator: Vess Oil Corporation

County: Rooks *117.85*

Address: 8100 E. 22nd Street North
Building 300
Wichita, Kansas 67226

Well total depth 3626 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 221 Feet
W/175 sxs.cmt.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 12 Month: May Year 1999

Plugging proposal received from: Joel Stull

Company: Vess Oil Corporation Phone: -

Were: Ordered 250 sxs 60/40 pozmix - 10% gel plus 500# hulls.
5 1/2" casing set at 3578' w/200 sxs cement.
Perfs at 3327' - 3628'.
T.O.F. 1600'.
Squeeze at 1045' w/180 sxs and 1300' to 1390' w/250 sxs.

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 20 1999
5-20-99
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 11:15 A.M., Day 12, Month: May, Year: 1999

Actual plugging report: R.U. Cementers and squeezed casing as follows:
25 sxs cement with 300# hulls mixed in cement followed with 200 sxs cement with 300# hulls
mixed in cement. Max. P.S.I. 300#.
R.U. Cementers to 8 5/8" S.P. Squeezed in 5 sxs cement - pressured up - blew out head.

Remarks: _____

Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES CALC , NO Dakota plug: YES , NO
Plugged through TUBING CASING Elevation: _____ G.L. _____

I did[] / did not[] observe the plugging.

MA
Dennis A. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 5-21-99

WEL. NO. 60968