

4-042005

2-17

15-163-

01554-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-95,139

W2 NE NE /4 SEC. 21, 09 S, 18 W
4620 feet from S section line
990 feet from E section line

Operator license# 5030

Lease: Paradise Creek Well # 204

Operator: Vess Oil Corporation

County: Rooks *116.78*

Address: 8100 E. 22nd St. North
Building #300
Wichita, Kansas 67226

Well total depth 3593 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 1495 Feet
W/750 sxs.cmt.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 17 Month: February Year 1999

Plugging proposal received from: Joel Stull

Company: Vess Oil Corporation Phone: -

Were: Ordered 350 sxs 60/40 pozmix - 10% gel plus 20 sxs gel and 300# hulls.
5 1/2" casing set at 3590' w/150 sxs cement.
O.H. 3578' - 3582'.
W.L.M. 3583'. Casing squeezed at 2759' - 2828' w/266 sxs cement.

2-23-99

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 10:00 A.M. , Day 17, Month: February , Year: 1999

Actual plugging report: RU cementer and squeezed casing as follows: 25 sxs cement with 300# hulls, followed with 20 sxs gel, followed with 25 sxs cement. Fluid started circulating from annulus. Continued pumping cement down casing to try to get cement to circulate annulus. Cement did not circulate annulus with 275+ sxs down casing. Shut-in annulus, casing pressured up immediately while pumping. Shut down and hooked-up to annulus. Squeezed 30 sxs cement down annulus. Max. P.S.I. 600#. S.I.P. 300#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING CASING X Elevation: G.L.

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 3-1-99

INV. NO. 60671