

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23150-00-00
Spot: NESWSW Sec/Twnshp/Rge: 21-9S-18W
990 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: WIDMAN Well Number: 6
County: ROOKS Total Vertical Depth: 3640 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 204 w/140 sxs cmt 8/118.30
Production: Size 5.5 feet: 3630 w/150 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/01/2001 3:00 PM

Plug Co. License No.: 5030 Plug Co. Name: VESS OIL CORPORATION

Proposal Rcvd. from: PAT CANADAY Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perf 1470' and squeeze with 275 sxs cement. Circulate up for 20 minutes and lost it.
100 sxs down braden head.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/01/2001 5:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perfs 3578' to 3596'.
Squeezed 8 5/8" S.P. at 1000# max.
Squeezed 5 1/2" casing - squeezed 25 sxs 60/40 pozmix - 10% gel with 200# hulls,
followed with 10 sxs gel, followed with 175 sxs 60/40 pozmix - 10% gel with 300# hulls.
Max. P.S.I. 1500#. S.I.P. 1000#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

RECEIVED

OCT 19 2001
10-19-01
KCC WICHITA

INVOICED

DATE 10-22-01

INV. NO. 2002060828


Form CP-2/3

OCT 17 2001

STATE KANS COUNTY ROOKS
 FIELD PARADISE CREEK (LANSING/ARBUCKLE)
 OPER LEAVELL RESOURCES
 WELL 6 WIDMAN
 API 15-163-23150-0000
 SPUD 03/09/1991
 DTD 3640 LTD FTD ARBUCKLE

WELL CLASS DO
 STATUS OIL
 COMP 05/13/1991
 PBTD

21-9S-18W
 NE SW SW
 990FSL 4290FEL SEC



LOC 2 MI NW PLAINVILLE, KS

Petroleum Information Corporation

IP IPP 12 BOPD 200 BW
 PROD ZONE: ARBUCKLE 3578-3596

EL: 2170 KB 2165 GR

CSGS: 8 5/8 @ 212 W/ 140 SACKS
 5 1/2 @ 3637 W/ 150 SACKS
 TBGS: 2 7/8 @ 3610
 DRLG COMP 3/14/91 RIG REL 3/15/91
 PERFS: ARBUCKLE PERF 3600-3602
 TREATMENT & TSTG RESULTS NOT RPTD
 SQZD 3600-3602 W/ 100 SACKS
 ARBUCKLE PERF W/ 2/FT 3578-3596 GROSS
 3578-3580 3584-3590 3592-3596
 ACID 1750 GALS 15% NE
 NO CORES

LOG TOPS:
 ANHYDRITE 1491 +679
 BSE ANHYDRITE 1528 +642
 TOPEKA LM 3069 -899
 HEEBNER SH 3289 -1119
 TORONTO LM 3308 -1138
 LSG-KANSAS CITY 3331 -1161
 BSE KANSAS CITY 3554 -1384
 ARBUCKLE 3577 -1407
 TD 3640 -1470

LOG TYPES: GRDL

OPER ADDRESS: 1032 E HWY 40, HAYS, KS 67601

CONTR: EMPHASIS OIL OPERATIONS RIG# 8

KS 5-070991

Copyright 1991 Petroleum Information Corporation