

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23134-00-00  
Spot: NESES<sub>W</sub> Sec/Twnshp/Rge: 21-9S-18W  
990 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: WIDMAN Well Number: 5  
County: ROOKS Total Vertical Depth: 3680 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Production Casing Size: 5.5 feet: 3674 150 SX CMT  
Surface Casing Size: 8.625 feet: 221 135 SX CMT

#119<sup>60</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/08/2003 8:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 885-4352

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/08/2003 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perf at 1400' - squeezed with 300 sxs cement.  
Squeezed at 1450' - 1490' w/100 sxs cement; squeezed at 2038' - 2090' w/150 sxs cement.  
Bridge at 2100'.  
RIH with tubing to 2030' - tubing stacked-out - ran 5 sxs gel ahead of cement, followed with 25 sxs cement and 200# hulls.  
Circulated to surface.  
Pulled tubing to 1450' and circulated cement to surface with 85 sxs cement plus 200# hulls.  
POOH with tubing and squeezed additional 15 sxs cement.  
Max. P.S.I. 600#. S.I.P. 600#.  
8 5/8" x 5 1/2" - pumped 5 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.

RECEIVED  
SEP 23 2003  
9-23-03  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

100-

Signed Dennis J. Hamel  
(TECHNICIAN)

INVOICED

DATE 9-23-03  
INV. NO. 2004060538

SEP 11 2003

STATE KANS COUNTY ROOKS  
FIELD PARADISE CREEK (LANSING/ARBUCKLE)  
OPER LEAVELL RESOURCES  
WELL 5 WIDMAN  
API 15-163-23134-0000  
SPUD 01/08/1991  
DTD 3680 FTD ARBUCKLE

WELL CLASS 990FSL 2970EEL SEC  
STATUS DO  
COMP OIL  
PBT 02/07/1991  
3640

21-9S-18W  
NE SE SW

+	+	+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+	+	+
+	+	+	+	+	+	+	+	+	+

LOC 1 3/4 MI NW PLAINVILLE, KS

Petroleum Information Corporation

IP IPP 20 BOPD 450 BW  
PROD ZONE: ARBUCKLE 3578-3580

EL: 2170 KB 2165 GR

CSGS: 8 5/8 @ 221 W/ 135 SACKS  
5 1/2 @ 3674 W/ 150 SACKS  
PERF FOR SQZ 3591-3606 GROSS  
TBGS: 2 7/8 @ 3635  
DRLG COMP 1/17/91 RIG REL 1/17/91

LOG TOPS:		
ANHYDRITE	1496	+674
TOPEKA LM	3071	-901
HEEBNER SH	3288	-1118
LSG-KANSAS CITY	3330	-1160
ARBUCKLE	3574	-1404
TD	3680	-1510

PERFS: ARBUCKLE PERF W/ 4/FT 3578-3580  
ACID 1500 GALS

NO CORES OR DSTS

OPER ADDRESS: BOX 308, HAYS, KS 67601

CONTR: EMPHASIS OIL OPERATIONS

KS 5-060491

Copyright 1991 Petroleum Information Corporation