

4-041946

12-8

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - N/A

SW SW NE /4 SEC. 21, 09 S, 18 W
2970 feet from S section line
2310 feet from E section line

Operator license# 5447

Lease: Paradise Creek Well # 201

Operator: OXY USA, Inc.

County: Rooks 116.51

Address: P.O. Box D
Plainville, Kansas 67663

Well total depth 3585 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 1500 Feet
W/400 sxs cmt.

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Co Tools License# 5447

Address: _____

Company to plug at: Hour: 9:00 A.M. Day: 8 Month: December Year 1997

Plugging proposal received from: J.D. Hininger

Company: OXY USA, Inc. Phone: 785-434-7681

Were: 5 1/2" casing set at 3572' w/150 sxs cement. Perfs. At 3367' - 3584'.
Ordered 350 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls plus 20 sxs gel.
Anhy. At 1500' - Dakota at 950'. W.L.M. at 3589'.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[X], None[]

12-17-97

Completed: Hour: 11:30 A.M., Day: 8, Month: December, Year: 1997

Actual plugging report: R.U. Cementers to 5 1/2" casing. Squeezed casing with 25 sxs 60/40 pozmix - 10% gel with 200# hulls, followed with 20 sxs gel, followed with 150 sxs cement with 300# hulls. Max. P.S.I. 300#. R.U. Cementers to 8 5/8" S.P. Squeezed with 175 sxs cement with 100# hulls. Max. P.S.I. 100#. Job complete.

Remarks: CK'd T.O.C. @ 500' - by w/add 65 sxs cmt w/100 # hulls - 12-9-97
Condition of casing(in hole): GOOD ___ BAD Anhy.plug: YES NO ___
Bottom plug(in place): YES , CALC ___, NO ___ Dakota plug: YES , NO ___
Plugged through TUBING ___ CASING . Elevation: ___ G.L. ___

I did[X] / did not[] observe the plugging.

Dennis J. Hamel
(agent)

INVOICED

DATE DEC 18 1997

INV. NO. 49745

12-8