

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-00410-00-01
Spot: E2SENE Sec/Twnshp/Rge: 29-14S-14W
3286 feet from S Section Line, 437 feet from E Section Line
Lease Name: RUSCH Well #: 1
County: RUSSELL Total Vertical Depth: 562 feet

Operator License No.: 33813 •
Op Name: JASON OIL COMPANY, LLC
Address: 3718-183RD ST. PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	5.5	562		w/100 sxs
PROD	7	3220	0	w/unknown sxs cmt
SURF	10.75	220	0	w/unknown sxs cmt

35.00

Well Type: SWD UIC Docket No: D19341.0 Date/Time to Plug: 02/08/2007 1:30 PM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVID FUNK Company: JASON OIL COMPANY Phone: (785) 483-3854

Proposed Plugging Method: 7" cement to surface with 380 sxs from 501'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/08/2007 2:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Pressured backside to 500# P.S.I. Held.
Pumped 25 sxs 60/40 pozmix - 10% gel cement.
Pumped 50 sxs cement with 200# hulls.
Max. P.S.I. 700#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
406	436		

INVOICED
DATE 3-27-07
INV. NO. 2007061507

Remarks: QUALITY CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Case Morris

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 19 2007
Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

MAR 12 2007

PST

WESTGATE-GREENLAND OIL CO #1
15-167-00410-0000

RUSCH

29-14-14
QAL 58 WE

Contr.

RUSSELL

County

EL 2813

Comm

5-7-41

Comp.

6-3-41

IP

3000 BOPD

Tops	Depth	Datum
TOP	2665	
LANS	2955	-1141
ARB	3218	-1404
TD	3225	-1411

Casing

10" 220

7" 3218

5/2" Liner To 562' w 100 SKS.

2700' OIH

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

