

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-03228-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 33-10S-23W  
4950 feet from S Section Line, 990 feet from E Section Line  
Lease Name: DIEBOLT B Well #: 9  
County: GRAHAM Total Vertical Depth: 3802 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3778	0	125 SX
SURF	8.625	218	0	175 SX

\$ 123.57

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/14/2007 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 800# hulls.  
Fluid 45' from surface.  
Bad casing - could not get below 1510'.  
Top of tubing fish 1510'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/14/2007 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1500'. Allied pumped 50 sxs cement, followed with 60 sxs cement with 200# hulls - circulated cement.  
PTOH. Allied squeezed with 165 sxs cement with 600# hulls.  
Shut in 30 minutes.  
Topped 5 1/2" casing off with 25 sxs.  
Max. P.S.I. 500#.  
Hooked up to backside and pumped 40 sxs cement.  
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3767	3771		
3750	3755		

INVOICED  
DATE 3-27-07  
INV. NO. 2007061510

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

MAR 19 2007

CONSERVATION DIVISION  
WICHITA, KS

MAR 15 2007

PCT

IMPERIAL OIL

#9 DIEBOLT

33-10-23W  
NW NE NE

Contr. IMPERIAL OIL

GRAHAM County

E 2351RB Comm. 3-12-56

Comp. 4-20-56

IP 166 BOPD/LANS

Tops	Depth	Datum
ANH	1855	496
HEEB	3544	-1193
LANS	3576	-1225
TD	3802	-1451

Casing  
 5" 3778  
 DST 3737-53/1 HR, 6' OCM,  
 BHP 50#: DST 3753-78/1 HR,  
 1620' GAS, 100' H OCM, 160'  
 OIL, BHP 530#:  
 DD 3802: PERF 26/3767-71  
 ACID 500: SWB 5 BOPH/10 HR  
 23/3750-55: ACID 4500: SWB  
 30 BOPH/8 HR  
 DIEBOLT


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS