

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20669-00-01

Spot: SWSESE

Sec/Twnshp/Rge: 5-14S-17W

338 feet from S Section Line,

1123 feet from E Section Line

Lease Name: HOFFMAN

Well #: 1

County: ELLIS

Total Vertical Depth: 1213 feet

Operator License No.: 8061

Op Name: OIL PRODUCERS INC. OF KANSAS

Address: 1710 WATERFRONT PARKWAY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1241	0	w/unknown sxs cmt
SURF	8.625	209	0	w/140 sxs cmt

\$ 39.42

Well Type: SWD

UIC Docket No: D22287.0

Date/Time to Plug: 03/19/2007 9:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: MIKE VANARSDALE

Company: OIL PRODUCERS INC. OF KANSAS Phone: (785) 623-3014

Proposed
Plugging
Method:

Ordered out 150 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/19/2007 12:30 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Swaged onto 4 1/2" - mixed and pumped 100 sxs with 450# hulls.
S.I.P. 200#.
Hooked up to the annulus - pumped 20 sxs with 50# hulls.
S.I.P. 200#.

INVOICED
DATE 3-27-07
INV. NO. 200 7061511

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

RECEIVED

MAR 23 2007

KCC WICHITA

MAR 20 2007

OIL PRODUCERS, INC. OF KANSAS
1346 N. WOODLAWN
WICHITA, KS 67208

"OWWO"
#1 HOFFMAN

5-14-17W
SW SE SE

CONTR MURFIN DRILLING COMPANY CTY ELLIS

GEOL FIELD YOUNGER

ELV 2024 KB SPD 8/1/83 CARD ISSUED 9/1/83 IP SWDW

CED HILLS 803-855

API 15-051-20,669-A

SMP	Tops	Depth/Datum
ANH	1216 +	808
B/ ANH	1253 +	771
TOP	3019 -	995
HEEB	3271 -	1247
TOR	3289 -	1265
LANS	3315 -	1291
BKC	3532 -	1508
CONG	3558 -	1534
ARB	3616 -	1592
RTD	3630 -	1606
NO LOG		

OLD INFO: OPERATOR WAS ARMSTRONG & JACKMAN, #1
HOFFMAN, SPD 9/28/70, SET 8 5/8 " 209/140SX, COMP. AS D&A
/ ARB 10/5/70, (CARD ISSUED 10/8/70), CONTR: ASPEN DRILLING
CO., GEOL: BOB ARMSTRONG
NO DST'S

NEW INFO: FR 8/3/83, RE-ENTERED 8/1/83, WSH DWN TO 1600,
LOST HOLE WHILE ATTEMPTING TO GO TO ARB & GR WSH, PB,
SET 4 1/2 " 1241; MICT - CO, PF (CED HILLS) 803-55, TSTD,
SWDW - INJECTION RATE SATISFACTORY

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS