

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21910-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 22-11S-22W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SHUBERT A Well #: 3
County: TREGO Total Vertical Depth: 4005 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67260

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4002	0	450 SX
SURF	8.625	248	0	165 SX

\$ 130.16

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2007 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: Ordered 260 sxs 60/40 pozmix - 10% gel - 500# hulls.
Junk in the hole - casing leaks.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/14/2007 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 1230'. Hit top of fish.
Rigged to tubing - pumped 85 sxs 60/40 pozmix to circulate cement out into pit area.
Pulled tubing - rigged to 4 1/2" casing with a swedge - pumped 15 sxs 60/40 pozmix.
Max. P.S.I. 500#. S.I.P. 450#.
Rigged to 8 5/8" and pumped 10 sxs 60/40 pozmix.
Max. P.S.I. 450#. S.I.P. 450#.

Perfs:

Top	Bot	Thru	Comments
3900	3914		OH

INVOICED

DATE 3-27-07

INV. NO. 2007061502

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #C-31620.

Plugged through: TBG

District: 04

Signed *Katueh*

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

MAR 19 2007

CONSERVATION DIVISION
WICHITA, KS

MAR 16 2007

PKT

replacement card

STRATA ENERGY RESOURCES CORPORATION
NEWPORT BEACH, CA 92629

22-11 -22W
NW SW SE

#3 SHUBERT

site: 5-3/4 N & 3/4 W OF OGALLAH, KS.
contr: REVLIN DRILLING, INC.
geol: BETH FUHR

city: TREGO
field: GAGELMAN SOUTH

API 15-195-21910

fr date 03/18/87 spd date 05/11/87 drlg comp 05/17/87 card issued 08/12/87 last revised 10/12/88

ELV: 2298 KBL LOG

tops.....	depth/datum
ANH.....	1758 +540
B/ANH.....	1798 +500
TOP.....	3328 -1030
HEEB.....	3540 -1242
TOR.....	3568 -1270
LANS.....	3580 -1282
BKC.....	3810 -1512
MARM.....	3892 -1594
ARB.....	3998 -1700
RTD.....	4005 -1707

IP status:

OIL, P 26 BO & 16 BWPD, MARM 3900-3914 OA,
INFO RELEASED: 10/12/88 - WAS OIL WELL - TIGHT HOLE
CSG: 8-5/8" 248 / 165 SX, 4-1/2" 4002 / 450 SX
NO CORES OR DSTS
MICT - CO, PF (MARM) 3900-3910 & 3910-3914, W / 2
SPF, AC 1500 GAL (15% DS/FE), FRAC'D (AMT NA),
GSO, SET 2-3/8" TBG AT 3889, POP, P 26 BO & 16
BWPD (GR 36), 7/5/87

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS