

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19181-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 36-14S-15W
970 feet from S Section Line, 2392 feet from E Section Line
Lease Name: HALL Well #: 1
County: RUSSELL Total Vertical Depth: 3215 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3210	0	w/unknown sxs cmt
SURF	8.625	810	0	w/unknown sxs cmt

\$ 104.49

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/22/2007 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 275-7461

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/22/2007 1:15 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Top of tubing at 3150'. Top of rods 1400'.
Perfed at 1400' and 810'.
Ran tubing to 1400' - circulated with 100 sxs 60/40 pozmix - 10% gel cement.
POOH. Pumped 20 sxs down backside.
Cement circulated up outside of surface pipe.
Tied onto casing - pumped 55 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 300#.

INVOICED
DATE 3-27-07
INV. NO. 2007061501

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Case Morris
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 19 2007
Form CT-2/3
CONSERVATION DIVISION
WICHITA, KS

MAR 12 2007

PST

STEARNS DRILLING

#1 HALL

36-14-15W
NW SW SE

Contr. STEARNS DRILLING

RUSSELL County


E 1788 ^{FB} Comm. Comp. 5-11-56 IP 25 BOPO

Tops	Depth	Datum
KC	2980	-1192
ARB	3210	-1422
ID	3215	-1427

Casing
8" 810
5" 3210

CO 3215: ACID 250

GORHAM POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS